

AMENDMENT TO SURVEY

Subject Survey: Survey Number 10196.

Location: Located in the southwest quarter of Section 6, Township 38 South, Range 2 West of the Willamette Meridian, Jackson County, Oregon.

Survey For: Mr. James C. Hoehn
7402 Dinsdale
Downey, California 90240

Purpose: A deed record call was mistakenly calculated as 743.00 feet, when its correct value is 750.00 feet.

Procedure: Using the correct deed dimension of 750.00 feet to control the east line of the tract surveyed on said filed survey no. 10196, I computed the correct positions for the northeast and southeast corners. This shift effects 6 dimensions on the formerly referenced filed survey. These dimensions being: (a) the deed record distance along the south line of O.R. 78-17732, (b) the measured distance along the south line of O.R. 82-17057 between monuments set and (c) the west line of Section 6, (d) the distance along the east line of O.R. 82-17057 and (e) the delta angle and (f) arc length of the curve at the northeast corner of O.R. 82-17057.

These corrections are listed below:

	<u>Original</u>	<u>corrected</u>
(a)	743.00	750.00
(b)	630.51	623.51
(c)	655.51	648.51
(d)	352.43	351.66
(e)	6°15'05"	5°32'44"
(f)	92.59	85.55

The above corrections have been noted on said filed survey no. 10196.

Surveyor: Kurt C. Weaver
616 China Gulch Road
Jacksonville, Oregon 97530

Date: October 11, 1985

