

10394

SEC. 12 T.38 S., R. 2 W

REC NORTH 5280.0' or 80.0 chs = 5298.56' Meas.

GLO = NORTH 2640.00' = 2649.28' P.P. DIST.

GLO. REC = NORTH 2640.0' = 2649.28' Measured

1/4 Corner

SEC. 7 T.38 S., R. 1 W.

SURVEY 1/4 COR. BETWEEN SEC. 7, T.38S., R. 1 W. &
SEC. 12, T.38S. R.2W., WM.
BY BOARD ORDER: JACKSON CO. COMM.

85-23

BY: EDWARD A. MCGINTY
JACKSON COUNTY SURVEYOR
COUNTY COURT HOUSE
MEDFORD, OREG

SCALE 1" = 400'
MONUMENT SEE HAR.
NOV. 13, 1985

** RECEIVED **
Date 11/14/85 By SK
This survey Consists of
1 sheet(s) Map
1 page(s) Narrative
JACKSON COUNTY
SURVEYOR

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Edward A. McGinty

OREGON
JULY 10, 1953
EDWARD A. MCGINTY
301

10394

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

SURVEYED FOR: Honorable Board of Commissioners
of Jackson County

SURVEYED BY: Edward A. McGinty
Jackson County Surveyor
County Courthouse
Medford, Oregon 97501

LOCATION: East quarter corner of Section 12, Township 36 South,
Range 2 West, also being the West quarter corner of
Section 7, Township 36 South, Range 1 West.

PURPOSE OF SURVEY: This survey was made in conjunction with Survey No. 10393,
as requested by the Board of Commissioners.

PROCEDURE:

The original monument for the quarter corner between Sections 7 and 12,
calls for a post set in a cultivated field, in January 1854. Presently and
for many years this position has been in an orchard. After diligent search
in county records and in the field for a monument, this corner position was
considered lost. The procedure for re-establishment of this corner was the
standard procedure of single proportional measurement from the nearest corner
North and the nearest corner southerly.

At the quarter corner between Sections 7 and 12, set an iron pipe, 1 inch
in diameter, 36 inches long, 6 inches in the ground with a brass cap 2½ inch
in diam. marked ¼ 12/7 CS 1985. For new references see County Surveyor's
official records.

At the section corner to Sections 1, 6, 7 and 12 and the section corner
to Sections 7, 12, 13 and 18, found monuments set in previous county surveyor
records. For additional information see official records of the County Surveyor.

DATE: November 13, 1985

**** RECEIVED ****
Date 11/14/85 By SL
This survey Consists of:
1 sheet(s) Map
1 page(s) Narrative
JACKSON COUNTY
SURVEYOR

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Edward A. McGinty
OREGON
JULY 10, 1953
EDWARD A. MCGINTY
301