

10438

DLC. 56

**\*\* RECEIVED \*\***  
 Date 12/31/85 By         
 This survey Consists of:  
  1   sheet(s) Map  
  1   page(s) Narrative  
 JACKSON COUNTY  
 SURVEYOR

Sec. 15

Sec. 14

Sec. 22

Sec. 23

Fd. 5/8" I. Pin

ROSS LANE

DLC. NO. 69

**REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR**  
*Edward A. McGinty*  
 OREGON  
 JULY 10, 1953  
 EDWARD A. MCGINTY  
 301

DLC 68

HANLEY

SW 69  
N89°46'10"E

ROSSANLEY

ENE 68

Gbvt Lot

N89°52'40"E  
428.25'

N89° 43'37" E 4905.15'

DLC 70

SE 69

NE 70

RE-ESTABLISHED CORNS. FOR DLC'S 68, 69, 70 T. 37S., R. 2W., WM.  
 FOR JACKSON CO

85-25

BY: Edward A. McGinty  
 Jackson County Surveyor  
 County Courthouse  
 Medford, Oregon

Scale 1" = 300'  
 ● = Fd. CS. Mon. (see  
 re-established corners)  
 December 19, 1985

10438

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250  
OREGON REVISED CHAPTER

SURVEY FOR: Jackson County

SURVEY BY: Edward A. McGinty  
County Surveyor

LOCATION: Re-established corners for Donation Land Claims 68, 69 and 70, Township 37 South, Range 2 West, Willamette Meridian, Jackson County, Oregon.

DATE: December 19, 1985

BASIS OF BEARING: Survey No. 3311, N89°52'40"E, South line DLC 69.

PURPOSE: The restoration of Donation Land Claim corners; Southwest corner of 69, East Northeast corner of 68 and the Northwest corner of 70.

PROCEDURE: All donation land claim corner monuments recovered were flush with surface with the exception of the Southwest corner of No. 69, which was approximately 5 ins. tilted northwesterly. This monument was reset and brass capped to it's previous position.

The 5/8 ins. iron pin 6 ins. deep shown on the west line of DLC 69 and the centerline of Ross Lane extended was set by me approximately 20 years ago as a reference point.

This map was made in conjunction with corner restoration which is intended as part of this narrative.

