



LEGEND:
 ●=FOUND MONUMENT AS SHOWN.
 ○=SET 5/8" IRON PIN WITH PLASTIC CAP STAMPED, MOFFIT PLS 944.
 BASIS OF BEARINGS:
 SURVEY NO. 7403

RECEIVED
 Date: 5/15/86 By: [Signature]
 This survey consists of:
 1 sheet(s) Map
 1 page(s) Narrative
 JACKSON COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR
 Lloyd R. Moffitt
 OREGON JULY 17, 1978
 LOYD R. MOFFITT 944

PLAT OF SURVEY FOR JACKSON CO. PARKS AND RECREATION
 BEING A PORTION OF D.L.C. NO. 56 IN SECTIONS 2, 11 AND 12, TOWNSHIP 37 SOUTH, RANGE 2 WEST, WILLAMETTE MERIDIAN JACKSON COUNTY OREGON
 SCALE: 1"=200'
 DATE: APRIL, 1986
 PREPARED BY: FRIAR-MOFFITT AND ASSOCIATES MEDFORD, OREGON

Survey No. 10553

Survey Narrative to comply with O.R.S. 209.250

Survey For: Jackson Co. Parks and Recreation
Jackson County Court House
Medford, OR 97501

Location: A portion of D.L.C. No. 56 in Sections 2,
11 and 12, Township 37 South, Range 2 West,
Willamette Meridian, Jackson County, Oregon.

Purpose: To survey and monument the parcel as shown
on the attached map.

Procedure: Using a combination of data shown on Survey
No. 376 and deed distances, the Northwest
corner of that certain parcel described in
Book 236, Page 240, Jackson County Official
Records, was determined. A line was ran from
said corner to the Southwest corner of the
East one-half of D.L.C. No. 56. This deter-
mined one of the Westerly lines of this survey.
The calls used for the North line of this
parcel, Book 527, O.R. Page 475, are the same
as shown on Survey No. 376, to the pipe found
on the West line of Hamrick Road. Using said
pipe I went West to intersect the West line
described above. This determined the North
line of this survey.
Pins set during Surveys 1431, 4758 and 166,
and monuments set on the I-5 Freeway Survey,
along with various recorded deed dimensions
were used to determine the other property lines
required for this survey.
A portion of the Westerly line was monu-
mented as instructed by the Department of Jackson
County Parks and Recreation.

Date: April, 1986

Loyd R. Moffit
Friar-Moffit & Associates
717 W. 10th St.
Medford, OR 97501

