


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established by Fred Rodolf, under Group Survey No. 18 in 1915. At the corner point: Set an iron post, 3 ft. long, 3 ins. diam., 24 ins. in the ground, for closing corner to Sections 17 and 18, with brass cap marked as shown in diagram. No trees available; raise a mound of stone, 5 foot base, 4 1/2 feet high north of corner; pits impracticable.



Description of corner evidence found:

Found a standard GLO. brass cap monument, marked as shown in diagram.

From which: A stone mound, 4 feet by 5 feet at base and 3 feet high bears N.11°31'E, 10.00 feet, record north of corner.

Description of monument and accessories I established to perpetuate the original location of this corner

I stabilize monument with stone collar around monument, clear brush and debris around monument and accessories. I mark the following accessories:

A fir, 11 inches in diameter, bears N.48°22'W., 42.90 feet distance, marked T41S R4W S18 LS 1071 BT

A fir, 15 inches in diameter, bears N.42°26"E., 32.00 feet distance, marked T31S R4W S17 LS 1071 BT

October 6, 1986

HAROLD L. CENTER
Registered Professional Land Surveyor
Oregon Certificate No. 1071



Office of County of

State of, I hereby certify that the within instrument was filed in this office for record on the day of; 19....., at o'clockm., (signed)

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/66)

