



B.L. Norris, Property  
 Portion of D.L.C. No 53  
 Sec. 10, T. 37S, R. 2 W, W. M.

Survey Narrative to Comply with Paragraph 209.250,  
Oregon Revised Statutes

For:  
B.L. Norris

Purpose:  
To establish the corners of an area bought by Mr. Norris. I was to use a legal description furnished by a Title Company to establish the lengths and bearings of the various courses of the area.

Procedure:  
From a survey made by Mr. Boyden I found some chain ties to locate the N.W. Corner of D.L.C. No. 53 in the center line of Taylor Road, also the bearing of the center line of Taylor Road. The description called for a south bearing from the D.L.C. corner. The corners were established as called for in the description, but there was a discrepancy in the east boundary between Pine Street and the point that lies 361.02' south of the N.E. corner. The description says there is a discrepancy in the east boundary-- it calls for a N 04° 30' E 850 feet. Using that description the corner would fall about 145 feet into an adjacent field, and would also add another course that did not show in the description. I found in the Deeds and Records several descriptions of the various courses of the property. Mr. Norris did not want to spend more money on the survey, but I believe that the east line I established is nearly correct and the closure is good. 2"x2" hubs with survey tacks were used to establish the corners.

REGISTERED  
OREGON  
LAND SURVEYOR

*Ralph J. Ellis*  
OCTOBER 4, 1957  
RALPH J. ELLIS  
416

RECEIVED  
JACKSON  
JAN 29 1958  
COUNTY  
ENGINEER-SURVEYOR