

March 11, 1987

10825

Jackson County Surveyor:

- Narrative of Monument at the S.E. Corner D.L.C. 42 -

This narrative is to inform you of the Monumentation of the Southeast Corner of D.L.C., #42, (Crater Lake & E. Main, City of Medford) T37S R1W W.M., Being also the centerline intersection of the above named streets.

FB#1301

1. We originally found in 1974, a 3/4" round pin.
2. June, 1984 we referenced this monument to the south on centerline of Crater Lake produced, to a .38 cal. shell in the South curb, 23.83 feet., and thence further South 9.80 feet to a 3/8" rod, 24" westerly of a 30" Sitkas Spruce tree. The backsight used at this time was the south monument at Jackson Street intersection.
3. June, 1985 we set a 1 1/2 in. iron pipe monument with a brass disc at 3" below the asphalt surface in a City of Medford "Monument" Case. From which a 1 1/2" brass disc was set at 27.00 feet south along the centerline of Crater Lake Avenue produced, to a point in the concrete sidewalk.
4. The afore mentioned 3/8" pin (R.P.) exists as of this writing.

FB#1555

Respectively Submitted,

C. Lind McBeth

C. Lind McBeth, L S. 565
City Surveyor
City of Medford

CM/gg

REGISTERED
PROFESSIONAL
LAND SURVEYOR

C. Lind McBeth
OREGON
JAN. 12, 1962
C. LIND MCBETH
565

