

Survey No. 10854

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.140
OREGON REVISED STATUTES

FOR: JACKSON COUNTY

LOCATION: Intersection of Antelope Road and Pacific Avenue.
Northeast quarter of Section 24, Township 36 South, Range 2 West, W.M.

DATE: January 9, 1987

BASIS OF BEARING: Survey No. 3294 N0°11'E Centerline of Pacific Avenue.

PURPOSE: In the last several years, there has been considerable damage to the county road pavement, caused by surveyors in digging sizeable holes in their attempt to recover this monument. Also this has created a hazard to the public who drive on this road. To remedy this, set a monument over the top and took new reference points.

PROCEDURE: Found, at the intersection of Antelope Road and Pacific Avenue in White City, 8 ins. below the asphalt surface of road, a 3½ ins. diameter brass cap set by the U.S. Army Engineers marked N52,609.50 - E92,579.91 elevation 1267.265.

Directly over found brass cap, set a 2½ ins. diameter brass cap, flush with the surface of road, in cement, marked:

€
|
€ — C.S.
1987

To perpetuate this location, take references as follows:

A fd. 5/8 ins. diam., punch mkd. rebar, fd. flush, brs. N50°15'E,
75.03 ft.

The center top stem of fire hydrant No. 23, brs. N60°13'E,
53.57 ft.

Chiseled cross atop corner of concrete curb, c. South and East,
brs. S30°02'E, 79.61 ft.

A fd. 5/8 ins. diam. rebar fd. flush with yellow plastic cap,
set on Survey No. 8835 in 1981, brs. N44°49'W, 70.74 ft.

Note: New brass cap measured 0.624 ft. above U.S.A.E. brass cap stamped "ELEV. 1267.265"; relative elevation of new brass cap is therefor 1267.889.

BY: R.Frost
D.Edwards

Approved by: Ed McGinty
Co.Surveyor

REGISTERED
PROFESSIONAL
LAND SURVEYOR

EDWARD A. MCGINTY
JULY 10, 1953
301

** RECEIVED **
Date 4/2/87 By SE
This survey Consists of:
0 sheet(s) Map
1 page(s) Narrative
JACKSON COUNTY
SURVEYOR