



SURVEY NO. 10863

- (8) Fd. iron pin 5/8 ins. diam., with plastic cap mkd. Jackson C.S. flush with surface.
- (9) Set iron pipe, 1 ins. diam., 36 ins. long, 16 ins. deep for witness corner of SSE corner of DLC 58 identical to the SSW corner of DLC 57.
- (10) Set iron pipe, 1 ins. diam., 36 ins. long, 14 ins. deep with plastic cap mkd. Jackson C.S. as reference point.
- (11) 19,341.315-19,728.816 Corner of DLC's SE57, NE58 R2W and NW38 R1W. No monument.
- (12) 19,341.353-19,708.816 Witness corner to (11). Set a iron pipe, 1 ins. diam., 36 ins. long with bronze disc. Mkd DLC witness corner CS 1987 flush with surface.
- (13) Set an iron pin 5/8 ins. diam., 12 ins. long, with plastic cap mkd. Jackson C.S. flush with pavement on the westerly line of Biddle Road and near the centerline of Gilman Street.
- (14) 21,794.791-17,552.574 NE corner of DLC 58, previously computed from old traverse.



SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

SURVEY FOR: Jackson County
Medford, Oregon

SURVEY BY: Edward A. McGinty
Jackson County Surveyor
County Courthouse Rm 306
Medford, Oregon 97501

LOCATION: Southeast quarter of Section 12, Township 37 South,
Range 2 West, of the Willamette Meridian in Jackson
County, Oregon. The DLC line between 57 and 59.

DATE: May 18, 1987

BASIS OF BEARING:

Determined from previous traverse points along the west
edge of pavement along Table Rock Road on Survey No. 9534.

PRECEDENCE OF SURVEY:

The purpose of this survey was to re-establish the Southeast corner of Donation
Land Claim No. 57, identical with the Northeast corner of Donation Land Claim
No. 59 (R2W) and the Northwest corner of Donation Land Claim No. 38 (R1W).

The procedure was first to establish the south-southwest corner of DLC 57,
being identical to the east-southeast corner of DLC 58, using record survey
angle from Table Rock Road centerline and at record distance from iron pipe
shown on Survey No. 11 of 95.70 ft. easterly, which determined the northern
position No. 1. Thence run northerly a record distance from point 7 as shown
on survey No. 11 of 268.00 ft., thence westerly to point opposite of point 1.
The difference being 0.08 ft. north and south. The DLC was established at mean
of these northern co-ordinates and holding 95.7 ft. from said pipe. The last
mentioned pipe is evident that over the years, this area has settled due to
erosion along the creek. The ground level is now about 2 ft. below normal,
which has caused the pipe to move or gradually shift northerly 0.40 ft. This
pipe has been in reasonably stable condition for the last several years
according to reference points the county had in 1981.

The procedure used to establish the DLC corners of the Southeast corner of 57,
the Northeast corner of 59 and the Northwest corner of 38, was identical to the
procedure on the first re-establishment, being on straight line and intersect-
ing the township line between Ranges 1 and 2 West.

From previous older airport traverse, co-ordinates were utilized to determine
some of the bearing and distances along the section line and to the northeast
corner of DLC 58.

CO-ORDINATES OF CORNERS AND MONUMENTS:

- (1) 20,154.570-19,731.583 $\frac{1}{4}$ corner to Sections 7 and 12. Fd. bronze disc
approximately 2 ins. below asphalt pavement.
- (2) 17,502.569-19,722.560 Sec. corner to Sections 12 and 13 Range 2 West and
Sections 7 and 18 Range 1 West. Fd. 3 ins. bronze disc.
- (3) 19,345.453-17,548.662 SSW corner of DLC 57, SSE corner of DLC 58. In
creek, no monument.
- (4) 19,338.513-21,204.923 NE corner of DLC 38, T37S,R1W. Fd. 2 $\frac{1}{2}$ ins. bronze
disc approximately 2 ins. deep.
- (5) 19,344.200-17,070.141 Record Survey No. 2287. Fd. 2 $\frac{1}{2}$ ins. bronze disc
in center of bridge and pavement.
- (6) Fd. 3/4 ins. pipe with 5/8 ins. iron pin inside cap with yellow plastic
cap mkd. Jackson C.S.
- (7) Fd. iron pipe 3/4 ins. diam., 8 ins. deep. Origin - Survey No. 11.