

10873

30
31
29
32

REC SUR 5034
N 1°00'33"E 2884.04 COMPUTED

(1)
N 14°35'E 130.49'
(2) ORIG. 1/4 COR SEC

1378.56'
1252.03'
N 0°19'35" W

REC SUR: N 0°22'19"E
1378.56'
1378.56'
2630.59' COMPUTED

19
20
29
30

AMENDED SURVEY NO. 5034
SECTION LINE 29/30 T.32 S., R.1 W. WM.
FOR
KOGAP LUMBER CO.
72-23

BY EDWARD MC GINTY
1467 OLEANDER ST
MEDFORD, OREGON
MAY 11, 1987

SCALE 1" = 500'
MONU. SEE 'NAR.

EDWARD A. MCGINTY
MAY 10, 1983
REGISTERED
PROFESSIONAL
LAND SURVEYOR
EDWARD A. MCGINTY

** RECEIVED **
Date: 5/26/87 By SKG
This survey consists of:
1 sheet(s) Map
1 page(s) Narrative
JACKSON COUNTY
SURVEYOR

10873

SURVEY NO. 10873

NARRATIVE

SURVEY NO. 5034 AMENDMENT

FOR: KOGAP MFG. CO.
2080 So. Pacific Hwy.
Medford, OR

BY: Edward A. McGinty
1467 Oleander St.
Medford, OR
May 11, 1987

This is not a resurvey or a retracement of the previous survey, but only an amendment to Survey No. 5034. This was done by utilizing previous co-ordinates and recovery of the traverse station nearby and by tying this to the re-established 1/4 corner. Between Sections 29 and 30, this was followed by recomputing distances and bearing from previous known co-ordinates.

Report on 1/4 corner between Secs. 29 and 30.

From conversation with Pruitt (ex-employee of Timber Products) he recalled of seeing scribe from the original B.T. The county surveyors employees made a very careful second search for evidence and found part of the original reverse scribe 1/4 S covered over with duff, approx. 7 ft. below the original pine tree (stump). This apparently came from down portion of tree. This tree was most likely felled on logging operation approx. 40 to 50 years ago. After a closer examination of the 1/4 corner stone, which was recovered, a faint but very clear 1/4 showed which was quite visible on the face of the stone.

