

April 16, 1987

10893

Jackson County Surveyor:

- Narrative of Monument change at the intersection of Biddle Road
and East Jackson Streets. -

1. The reason for change, is because of the new overlay of East Jackson Street, and an obscure ordinance of the Oregon Dept. of Transportation ruling.
2. The old monument was a concrete blob of approximately 12" diameter and 18" long with a Brass Disc, set at 8" below the surface, encased with a steel mon. case, with a lid at the surface. 1974
3. The new monument is a blob of concrete more or less in a cone shape ranging from 8" diameter at the bottom to 18" diameter at the surface, 24" deep, with a 2" diameter steel pipe 20" long encased within the concrete with a plastic sleeve, approximately 8" in diameter. The steel pipe has a Brass Disc anchored within its top approximately 3" below the surface with an iron monument case and lid at the surface. 1987
4. The references to this monument are a punch mark with a cross in the tops of the anchor bolts for the signal poles. The references are as follows:

Signal Pole Location	Bolt Location	Distance
1. Southwest	Northwest	37.76
2. Southeast	Northeast	35.60
3. Northeast	Southeast	49.64

The above mentioned references can be found on record in City of Medford Field Book #1433, Page 16.

Respectively Submitted,



C. Lind McBeth
City Surveyor
City of Medford

CB/gg