



N  
 SCALE 1"=200'  
 Basis of Bearings R.S.No. 7913  
 ○ = Set 5/8" x 24" I. Pin (tagged RLS No. 638)  
 ● = Fd. 5/8" I. Pin per R.S. 7913 (unless noted otherwise)

REGISTERED  
**PROFESSIONAL**  
 LAND SURVEYOR  
*George Burrell*  
 OREGON  
 JULY 10, 1984  
 GEORGE R. BURRELL  
 638

**MAP OF SURVEY**  
 Located in Section 31, T38S, R3E  
 For: JIM MILLER  
 By: George Burrell, R.P.L.S.  
 June 5, 1987

\*\* RECEIVED \*\*  
 Date 7/22/87 By      
 This survey consists of:  
 / sheet(s) Map  
 / page(s) Narrative  
 JACSON COUNTY  
 SURVEYOR

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR:

Jim Miller  
 P.O. Box 1088  
 Ashland, Oregon 97520

PURPOSE:

To monument and mark the South and West boundary of the E1/2 of the N.W. 1/4 and the East boundary of the W 1/2 of the N.E.1/4 of Section 31, T 38 S, R3E.

PROCEDURE:

A random traverse was run between the East, West and North 1/4 corners and the N.W. corner of said section 31. The monuments as established by recorded survey no. 2297 were tied to as shown on the accompanying map. The center 1/4 corner of said section 31 and the East 1/16 corner to section 30 and 31 as established by said survey no. 2297 were held as monumented. Surveyor Ramsey in the course of recorded survey no. 2297 apparently overlooked the fact that section 31 is located on the West boundary of the Township when he located the C.W. 1/16 and the W 1/16 corner to section 30 and 31 at a mid point position.

The C.W. 1/16 and the W 1/16 corner between section 30 and 31 was proportioned as shown on the accompanying map. The position as established for these two corners is in close agreement with an old N-S fence line. The boundary lines between monuments were marked with wood stakes.

BY:

George Burrell, R.P.L.S.  
 1379 Brookdale  
 Medford, Ore. 97501

June 5, 1987

**\*\* RECEIVED \*\***  
 Date 7/22/87 By SK  
 This survey consists of:  
1 sheet(s) Map  
1 page(s) Narrative  
 JACKSON COUNTY  
 SURVEYOR

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR  
*George Burrell*  
 OREGON  
 JULY 10, 1964  
 GEORGE R. BURRELL  
 638

Tax Lot No. 7100-38-3E-31