



Survey For  
**Sam Gilbert**  
 in the  
 SW 1/4, Sec. 15, T36S, R4W, W.M.  
 Lot 8 & Fractional Lot 9.  
 Corner & Sabin's Addition to Woodville  
 City of Rogue River, Jackson County, OR

Survey by  
 Malcolm N. Clark L.S. 601  
 329 N.E. 6th Street  
 Grants Pass, Oregon  
 503-479-0143

Legend

- Found 5/8" Pin with yellow cap Set in Survey # ----
- Set 5/8"x30" rebar with red cap mkd "LS 601"
- (DATA) Record data; filed surveys
- #---- Filed Survey Number
- \*-\*-\* Fence

Scale 1"=50'  
 July 29, 1987

**REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR**  
*Malcolm N. Clark*  
**OREGON  
 JULY 12, 1983  
 MALCOLM N. CLARK  
 601**

\*\* RECEIVED \*\*  
 Date 8/3/87 By SK  
 This survey consists of  
1 sheet(s) Map  
1 case(s) Narrative  
 JACKSON COUNTY  
 SURVEYOR

10937

SURVEY NARRATIVE  
O. R. S. 209.250

SURVEY FOR: Sam Guilbert  
3075 Wards Creek Road  
Rogue River, OR 97537

SURVEY BY: Malcolm N. Clark, L.S. 601  
329 N.E. 6th Street  
Grants Pass, OR 97526-0105

LOCATION: Tax Lot 36 4W 15CC 2101  
Lot 8 & Fractional Lot 9, of Carner and  
Sabin's Addition to Woodville in the  
SW 1/4 of Section 15, Township 36 South,  
Range 4 West, Willamette Meridian.  
City of Rogue River, Jackson County, OR

DATE: Set property corners on July 29, 1987.

EQUIPMENT: Wild T-16 Theodolite and Wild DI-4  
Distomat EDM

PURPOSE: To monument the corners of the above Tax  
Lot.

BEARING BASE: The Centerlines of Broadway and Second  
Street; the measured bearings as shown on  
Filed Survey Number 6746.

PROCEDURE: I tied the street intersections as set in  
Filed Survey number 6746 and used the  
measured bearings of the centerlines of  
Broadway and Second Street as the bearing  
base. I then computed the exterior cor-  
ners of Block 5 and proportioned the  
Northwest Corner of Lot 8 of Block 5. The  
bearings shown on the accompanying map of  
survey along the East and West boundaries  
of Lot 8 and Fractional Lot 9 are to the  
monuments set by Edwards in Filed Survey  
Number 9298 and not to the true position  
of the corners.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Malcolm N. Clark*

OREGON  
JULY 12, 1963  
MALCOLM N. CLARK  
601

\*\* RECEIVED \*\*  
Date 8/3/87 By SK  
This survey Consists of  
1 sheet(s) Map  
1 page(s) Narrative  
JACKSON COUNTY  
SURVEYOR