

Survey Narrative

10941

N.C.L. - MAIN ST. (ROGUE RIVER) SEC.
FAS A368 (N. Pine St.)
JACKSON COUNTY

MAP REFERENCE
DRAWING 9B-17-10

The purpose of this survey was to establish a new center line for reconstruction of N. Pine St. through the subject section. In connection with this survey, additional permanent easements were established and acquired.

Basis of Bearing: Pine Street as shown on Survey No. 6746, 6747, and 6787. Jackson County surveyor had Survey No. 7506 along same line in December 1977, tying in some of the identical monuments and found most of the monuments east of the presently indicated surveys indicating monuments may have been set in unstable pavement with the traffic of heavy log trucks gradually forcing monuments easterly or the monuments were not set properly at the time of survey.

May 8, 1987 -- Jackson County surveyor made Survey No. 10871. During this survey he found that only one intersection had two reference points by the County (except for quarter corner). Most references were destroyed by the adjoiners or OSHD reconstruction. On Survey No. 10871 the center station by Jackson County Road Department is shown in brackets, beginning at section corner and then actual remeasurement is shown alongside.

This survey was conducted in the following location: Section 15 and 16, Township 36 South, Range 4 west of the Willamette Meridian in the City of Rogue River, Jackson County, Oregon.

Date of Survey: July 16, 1987

Survey by: Oregon Department of Transportation
Highway Division
P. O. Box 1128
1523 S.E. Jackson
Roseburg, Oregon 97470

