

Survey No. 11350

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250.

Survey for: Mr. Stuart Hinson
4020 Little Applegate Road
Jacksonville, Oregon 97530

Location: Located in the northwest quarter of Section 32,
Township 37 South, Range 2 West of the Willamette
Meridian, City of Jacksonville, Jackson County,
Oregon.

Purpose: To monument Lot 8 as shown on the accompanying
map.

Procedure: I tied the controlling monuments as shown on the
accompanying map. I did not find any record of the
5/8 inch iron pin at the intersection of 4th and
E Streets. It is on line with the other monuments
on E Street including the 3/4 inch iron pin at the
center line of 5th and E streets, not shown on my
map because I did not measure a distance to it. I
proportioned the intersection of D and Oregon
Street using the record distances between California
and E Street along Oregon Street as per the City
of Jacksonville Plat. A bearing bearing intersection
of D and Oregon Street did not agree with original
dimensions of the block, so I rejected this method.
I then proportioned in Lot as shown on the accompa-
nying map.

Bearing is based on the center line of Oregon
Street as per filed survey no. 1963.

Surveyed by: Farber Surveying
P.O. Box 1311
Jacksonville, Oregon 97530

Date: December 14, 1987

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Herbert A. Farber

OREGON
JULY 26, 1983
HERBERT A. FARBER
2189

** RECEIVED **
Date 12/17/87 By SK
This survey Consists of
1 sheet(s) Map
1 page(s) Narrative
JACKSON COUNTY
SURVEYOR