

6011

1109

Survey For  
 D. J. CLIFFORD  
 Located in Lot No. 2 of  
 VAWTER SUBDIVISION  
 Sec. 1, T.38S.R.2W., W.M.  
 By: Mark E. Boyden  
 Apr. 1958.



Scale: 1" = 100'

• Set 5/8" iron pin

Fd. 1-1/2" iron pipe  
set in concrete

CROOKED CREEK ROAD

STAGE

N. 76° 11' 30" W. ROAD 989.1'  
 154.04'

(Plot N. 76° 40' W. SOUTH 993.53')  
 407.52'

S. 10° 10' 30" W. 190.37'

N. 10° 10' 30" E. 253.23'

S. 54° 32' E. 170.04'

E. N.I.D. West Canal

N.E. cor. Lot 3 VAWTER  
 SUBDIVISION  
 Fd. 1-1/2" iron pipe  
 set in concrete

REGISTERED  
**OREGON**  
 LAND SURVEYOR

*Mark E. Boyden*

NOVEMBER 8, 1951  
 MARK E. BOYDEN

201

Survey Narrative to comply with Paragraph 209.250,  
Oregon Revised Statutes

FOR: D. J. Clifford

PURPOSE: To monument and describe a parcel in the Northeast corner of the Clifford ownership in Lot No. 2, VAWTER SUBDIVISION in Section 1, Township 38 South, Range 2 West.

PROCEDURE: Found the monuments fronting Stage Road South of VAWTER SUBDIVISION to control the Northerly property boundary. Then monumented the Easterly boundary of the surveyed parcel on the Deed Record tie and Deed Record angle from the Northeast corner of Lot No. 3 of said Subdivision as called for in the adjacent property described in Jackson County Deed Records Volume 353, Page 339.

Meridian of solar origin was obtained from the bearings reported on Recorded Survey No. 659.

April 1958

