



**** RECEIVED ****
 Date: 1/21/88 By: [Signature]
 This survey consists of
 1 sheet(s) Map
 1 page(s) Narrative
 JACKSON COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR
Darrel W. Edwards
 OREGON
 JULY 9, 1968
 DARREL W. EDWARDS
 741

SURVEY FOR: Larry Smith		
SCALE: 1" = 200'	● Monuments Found as noted	DRAWN BY: D.W.E.
DATE: Dec. 11, 1987	○ Set 5/8" x 24" Steel Pin w/ Plastic Cap	RSN: Recorded Survey No.
LOCATION: SE 1/4 of Section 3, T. 34 S., R. 1 E. W.M., Jackson County, Oregon.		
SURVEY BY: Darrel W. Edwards 2000 Brookhurst # 27 Medford, Oregon 97504 Phone 776-2313		DRAWING NUMBER

SURVEY NO. 11091

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

SURVEY FOR: Larry Smith
5890 Crowfoot Road
Trail, Oregon

LOCATION: The Southeast 1/4 of Section 3, Township 34
South, Range 1 East of the Willamette Meridian
in Jackson County, Oregon.

PURPOSE: Survey property lines per deed records and
establish proposed property line for a Lot
Line Adjustment.

PROCEDURE: Monuments found and used for control for this
survey are as shown and described on the accom-
panying plat. Position of all section corners
and quarter section corners verified from
existing bearing trees. Traversed between
necessary corners pertinent to Section 3 in
order to subdivide the Southeast quarter.
Closed traverse survey ran around parcel West
of Crowfoot Road and parcel East of Crowfoot
Road described in Document No. 84-07090,
Jackson County Deed Records. Set survey
markers as shown on the accompanying plat.
Set 5/8" x 24" steel pins with yellow plastic
caps stamped "DW EDWARDS- PLS 741.

EQUIPMENT: Lietz TM 20-C theodolite, Lietz Red-1 EDM
and 200 foot steel tape.

BASIS OF BEARINGS: Recorded Survey No. 9093.

DATE COMPLETED: December 11, 1987

SURVEY BY: Darrel W. Edwards
2000 Brookhurst #27
Medford, Or. 97504
phone 776-2313

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Darrel W. Edwards

OREGON
JULY 8, 1966
DARREL W. EDWARDS
741

