

SURVEY NO. 11106

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

SURVEY FOR: Pacific Northwest Bell Telephone Company
132 West 4th Street
P. O. Box 730
Medford, Oregon 97501

LOCATION: Tax Lot 1500, Map 39 1E 5DA
Lying within Lot 7, Block 11 of the City of Ashland, Oregon, and
being in the Southwest Quarter of Section 4, Township 39 South,
Range 1 East, Willamette Meridian, Jackson County, Oregon

PURPOSE: To monument the southeast line of a 5' x 8' telephone company
easement.


EQUIPMENT: Lietz Set 4 Total Station

PROCEDURE: Block 11 of the City of Ashland, according to the official 1888
map thereof, has been surveyed by Recorded Survey 8565, and then
again by surveys 8610 and 10588. We have used the bearing for
Van Ness Street on RS8565 as our basis of bearings.

Comparing O.R.87-05215 with older deeds for Tax Lot 1500 and the
deeds for Lot 6 (Tax Lot 1600), it is apparent that the
northwest line of Tax Lot 1500 is the northwest line of Lot 7,
Block 11.

We have used the bearings and prorated distances on RS8565
(which are substantiated by RS8610 and RS10588) to determine the
location for the northwest line of Lot 7. From the calculated
lot line location, we then set the monuments shown on the
easement line 8 feet southeasterly from and parallel with the
northwest line of Lot 7.

March 17, 1988



REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert Joseph Milts

OREGON
SEPTEMBER 23, 1977
ROBERT JOSEPH MILTS
No. 1270

MARQUESS & ASSOCIATES, INC.
1120 East Jackson Street
P. O. Box 490
Medford, Oregon 97501

Robert Joseph Milts

Robert Joseph Milts
Professional Land Surveyor

PNB Job 88-79321
MAI Job 1-3416