



SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250FOR:

Frank Palacios  
P.O. Box 408  
Talent, Oregon 97540

PURPOSE:

To monument and describe the 5.20 Acre tract as shown on the accompanying map for lot line adjustment purposes. To monument and describe the existing fence along the Northerly boundary of the tract described in Vol. 87, Page 166 of the Deed Records of Jackson County, for boundary line agreement purposes.

PROCEDURE:


The centerline of Anderson Cr. Road was established between the found D.L.C. monuments as shown. The East boundary of said 5.20 Acre tract was established by holding the found 1/2" iron pin per R.S. No. 3545 and turning record angle off the D.L.C. line.

The East boundary of the tract described in Vol. 87, Page 166 was located deed record distance from the S.W. corner of D.L.C. No. 66, thence following the West bank of an old irrigation ditch. This East boundary as monumented was also included in the boundary line agreement description to clear any future confusion.

The remaining boundaries of said 5.20 Acre tract were located according to the clients instructions.

BY:

George Burrell, R.P.L.S  
1379 Brookdale  
Medford, Oregon 97504 Mar. 8, 1988



Tax Lot No. 500-38-1W-34

