

SURVEY NO. 11100

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: BOISE CASCADE CORP.
P.O. Box 100
Medford, Oregon 97501

SURVEY BY: Gary D. Kaiser
24015 Hwy. 140
Eagle Point, OR. 97524

LOCATION: Section 3, T33S, R1E, WM., Jackson County, Oregon

BASIS OF BEARINGS: Solar Observations

DATE: April 29, 1988

PURPOSE: To run the East - West centerline of Section 3 and set witness corners for the center-east and center-west 1/16 corners.
Also to mark the East - West centerline of Section 3 between the above mentioned witness corners. This boundary was marked with blazed and painted trees and B.C.C. property line tags nailed to the base of trees, on stumps and on logs. Also painted rock outcrops on the line being marked.

PROCEDURE: Utilizing EDM equipment, ran a random traverse from the East $\frac{1}{4}$ corner to the West $\frac{1}{4}$ corner running near the line to be marked. The distances were double measured and the compliment angles turned.
The witness corners were monumented and referenced as shown on the annexed map.

A theoretical subdivision of section 3 was computed utilizing an accumulation of bearings and distances determined on previous surveys by Boise Cascade personnel and the B.L.M. encompassing the East, North and West boundaries of said section 3. I developed a closure utilizing these previous surveys running from the East $\frac{1}{4}$ corner North to the NE corner of section 3, thence West to a proportionate position for the North $\frac{1}{4}$ corner, thence continue West to the NW corner of section 3 and thence South closing on my position for the West $\frac{1}{4}$ corner 3.9' South and 0.1 East. I have no previous survey information (other than the original notes) to develop a position for the South $\frac{1}{4}$ corner, which is monumented in its original position, but I was able to determine positions for the SE and SW corners of section 3. For my theoretical subdivision I used a proportionate position for the South $\frac{1}{4}$ corner, which because of the stubbing by the original surveyor on East-West section lines in this area, I am sure is very weak. From these controls theoretical positions for the center-east and center-west 1/16 corners were computed. Witness corners were set 50 feet toward the center of section 3 from the theoretical positions.

**** RECEIVED ****
Date 5/10/88 By JK
This survey Consists of
1 sheet(s) Map
1 page(s) Narrative
JACKSON COUNTY
SURVEYOR

REGISTERED
**PROFESSIONAL
LAND SURVEYOR**

Gary D. Kaiser

OREGON
JULY 16, 1967
GARY D. KAISER
No 803