



BASIS OF BEARINGS: R.S.N. 4798

Document No.  
77-16812  
Official Records

SURVEY BY: Darrel W. Edwards  
1014 East Pine  
Central Point, Oregon  
Phone: 664-1539

\*\* RECEIVED \*\*  
Date 8/1/88 By DL  
This survey consists of:  
1 sheet(s) Map  
1 page(s) Narrative  
JACKSON COUNTY  
SURVEYOR

SURVEY FOR: <i>Steve Mckeown</i>	
LOCATION: <i>In the East 1/2 of Section 32, T.39 S., R.2W,W.M. in Jackson County, Oregon</i>	
● Indicates monument found as noted	
○ Indicates 5/8"x 24" steel pin w/plastic cap set	
( ) Indicates Deed Record except where noted	
x—x—x Fence	R.S.N. = Recorded Survey Number
DATE: June 24, 1988	SCALE: 1" = 200'

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Darrel W. Edwards*  
OREGON  
JULY 9, 1969  
DARREL W. EDWARDS  
741

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250, OREGON REVISED STATUTES.

SURVEY FOR: Steve Mckeown

LOCATION: In the East 1/2 of Section 32, T. 39 S., R. 2 W., W.M., in Jackson County, Oregon.

PURPOSE: To locate and monument the boundaries of the client's property as described in Document No. 77-16812, Official Records.

PROCEDURE: Tied together by traverse the East 1/4 corner and the center 1/4 corner. Set the CE 1/16 corner midway between the two and double blaze the following trees as references thereto:

White Oak, 5" diam., bears S.78°28'25"E., 22.96' to a nail in side center.

White Oak, 7" diam., bears N.14°09'25"W., 59.99' to a nail driven in side center.

Thence traversed Northerly and tied to the East 1/16 corner between Sections 29 and 32 as established by recorded survey number 6356. Using this control, surveyed the property lines and set monuments as shown on the accompanying plat.

Monuments set are 5/8" x 24" steel pins with yellow plastic caps mkd. "DW EDWARDS PLS 741",

EQUIPMENT: Lietz TM-20C theodolite and Lietz Red-1 E.D.M.

BASIS OF BEARINGS: Recorded Survey Number 4798.

DATE COMPLETED: June 24, 1988

SURVEY BY: Darrel W. Edwards  
1014 East Pine St.  
Central Point, OR. 97502  
Phone: 664-1539

