



SCALE 1"=60'
 Basis of Bearings R.S. No. 5496
 ● = Set 5/8"x24" I. Pin (tagged R.L. S638)

MAP OF SURVEY

Located in N.E. 1/4 Section 29, T40S, R2E
 For: DONALD JELLUM
 By: George Burrell, R.P.L.S. 8/5/88

REGISTERED
PROFESSIONAL
LAND SURVEYOR
George Burrell
 OREGON
 JULY 10, 1984
 GEORGE R. BURRELL
 238

**** RECEIVED ****
 Date 8-29-88 By SK
 This survey consists of:
 + sheet(s) Map
 - page(s) Narrative
 JACKSON COUNTY
 SURVEYOR

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR:

Donald Jellum
8908 John Day Drive
Gold Hill, Oregon 97525

PURPOSE:

To mark the West boundary of tax lot no. 104 and the East boundary of tax lot no. 105-40-2E-29.

PROCEDURE:

The West boundary of tax lot no. 104 was run between the C.N. 1/16 section corner as monumented by Recorded Survey No. 5496 to the North 1/4 corner of Section 29, setting wood stakes approx. 200' apart.

The East boundary of tax lot no. 105 was run from the S.E. corner as monumented by Recorded Survey No. 8229 and parallel to the N-S centerline of section 29, setting wood stakes approx. 200' apart. The N.E. corner of tax lot no. 105 was monumented at record bearing (Recorded Survey No. 5496) and Deed Record distance from the North 1/4 corner of section 29. This position may not be exactly on the section line, as I did not run to the N.E. corner of section 29. The client was more interested in the position of his East boundary and not concerned with a small error in N-S position at the N.E. corner.

BY:

George Burrell, R.P.L.S.
1379 Brookdale
Medford, Oregon 97504

Aug. 5, 1988

Tax Lots 104 and 105-40-2E-29

REGISTERED
PROFESSIONAL
LAND SURVEYOR

George Burrell

OREGON
JULY 10, 1964
GEORGE R. BURRELL
529

