



Survey for
Ronald Ramage

in the
SE 1/4, Section 16, T.36S., R.4 W., W.M.

City of Rogue River, Jackson County, OR
Scale: 1" = 50' August 15, 1988

Survey by: Malcolm N. Clark, L.S.
Contact Real Estate Services, Inc.
404 NE "E" Street
Grants Pass, OR 97526
(P.O. Box 1287) Ph. 479-0143

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Malcolm N. Clark
OREGON
JULY 12, 1983
MALCOLM N. CLARK
601

** RECEIVED **
Date 9-19-88 By: [Signature]
This survey consists of:
— sheet(s) Map
— page(s) Narrative
JACKSON COUNTY
SURVEYOR

Legend

- Found Monument as noted
- Set 5/8" X 30" rebar/Red Cap LS 601
- () Record Data
- # Filed Survey Number

11320

SURVEY NARRATIVE
O. R. S. 209.250

SURVEY FOR: Ronald Ramage
6382 East Evans Creek Road
Rogue River, Oregon

SURVEY BY: Malcolm N. Clark, L.S. 601
Contact Real Estate Services, Inc.
404 N.E. E Street
Grants Pass, OR 97526

LOCATION: In the Southeast 1/4 of Section 16, Township 36 South,
Range 4 West, W.M.: Tax Lot 701, Tax Map 36 4W 16DD, in
the City of Rogue River, Jackson County, Oregon.

DATE: Set property corners on August 15, 1988

EQUIPMENT: Wild T-16 Theodolite and Wild DI-4 Distomat EDM.

PURPOSE: To monument the property corners of Tax Lot 701.

BEARING BASE: The centerline of Bergland Street between Third and
Fourth Streets, as shown on Filed Survey Number 6747, by
Robert B. Wiegand.

PROCEDURE: Using the record data from Filed Survey Number 6747, the
Centerline of Bergland Street was established. The
distances along the East line of Bergland Street were
proportioned, using the Plat of Bergland Addition as the
record distance. The lot depth was set deed record
distance.

