



- () INDICATES 1880 PLATTED RECORD
 - INDICATES LINE BLAZED & PAINTED w/ RED PAINT
 - ⊕ INDICATES MONUMENT FOUND AS SHOWN
 - INDICATES 5/8 "x 30 " REBAR w/ YELLOW PLASTIC CAP MARKED "TEMPLIN RLS 2359" SET.
- BASIS OF BEARING, BASED UPON SOLAR OBSERVATION.

*** RECEIVED ***
 Date: 10-26-88 by SK
 This survey consists of:
 ___ sheet(s) Map
 ___ page(s) Narrative
 JACKSON COUNTY
 SURVEYOR

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
R. G. Templin
 OREGON
 JUL 25, 1988
 RICHARD G. TEMPLIN
 2389

RICHARD TEMPLIN LAND SURVEYING
 2042 Sandra Pl. 776-0991 Medford, Oregon
PLAT OF SURVEY
 LOCATED IN
 SECTION 2, T.38 S., R.2 E., W.M., JACKSON COUNTY, OREGON
 SURVEY FOR: Boise Cascade Corp. DATE: Oct. 25, 1988

RICHARD G. TEMPLIN
PROFESSIONAL LAND SURVEYOR
2042 Sandra Pl.
Medford, Oregon 97504
(503) 776-0991

SURVEY NO. 11359

SURVEY FOR: Boise Cascade Corporation
North Pacific Highway
Medford, Oregon

Location: Section 2, Township 38 South, Range 2 East,
Willamette Meridian, Jackson County, Oregon.

Purpose: To monument the Center 1/4 Corner and the
Center North 1/16 Corner of Section 2, T.38S.,
2E., W.M. and to mark the true line between
said corners.

Date: October 25, 1988

**Basis of
Bearing:** Based upon Solar Observation

Procedure: Utilizing a Wild T-2, Wild T-16 and Mac 1E
EDM, tied North-East-South-West Quarter
Corners in by random traverse. At computed
position for Center One Quarter Corner set
5/8"x30" rebar from which I scribed the
following bearing trees:

A Douglas Fir, 6" diameter bears North 16°
East, 30.7 feet, scribed "C1/4RLS2359" "BT".
A Douglas Fir 7" diameter bears South 63°
West, 50.3 feet, scribed "C1/4RLS2359" "BT".

I then set the Center North 1/16 Corner with
a 5/8"x30" rebar, from which I scribed the
following bearing trees:

A White Fir 6" diameter bears South 43°
East, 33.9 feet, scribed "CN1/16RLS2359" "BT".
A White Fir 6" diameter bears South 35°
West, 11.4 feet, scribed "CN1/16RLS2359" "BT".

True line was marked between CN 1/16 Corner
and C 1/4 Corner with blue flagging and
blazed trees along said true line.

**** RECEIVED ****

Date 10-26-88 By SL

This survey Consists of:

1 sheet(s) Map

1 page(s) Narrative

JACKSON COUNTY
SURVEYOR

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Richard G. Templin

OREGON
JULY 26, 1988
RICHARD G. TEMPLIN
2359