

11391

AFFIDAVIT OF CORRECTION


The correction being made herein is in reference to the proportional 1/4 Section corner common to sections 4 and 5, Township 40 South, Range 3 East, as monumented by me and recorded as Survey No. 4269 in the Jackson County Surveyor's Office.

It was brought to my attention by Surveyor Herb Farber that the physical position of said 1/4 corner monument is located 10.00 feet North of the position as shown on said Recorded Survey No. 4269. An examination of my field notes revealed a error in calculating the tie from my control point to said 1/4 corner monument. In inversing the tie I inadvertently entered the North coordinate for said corner 10.00 feet too far North.

To correct this error, I physically moved the monument (a 1" G.I. Pipe) 10.00 feet Due South. The data as shown on the map of said Survey No. 4269 is correct. The correction applies only to the physical location of said 1/4 corner monument. However, the narrative for said survey is herein being corrected to reflect the correct bearing and distance to the bearing tree's as marked by said survey as follows: The 6" Fir now bears N 27° 33' W 12.9 feet; the 18" W. Oak bears N 31° 07' E 14.8 feet.

Nov. 9, 1988

George Burrell, R.P.L.S.
1379 Brookdale Road
Medford, Oregon 97504



CERTIFICATION

I, Edward A. McGinty, Jackson County Surveyor, hereby certify that I have examined this Affidavit of Correction, and that the changes are permitted in accordance with the Oregon Revised Statutes 209.255.

Edward A. McGinty
Edward A. McGinty
Jackson County Surveyor

