

SURVEY NO. 11427

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250  
OREGON REVISED STATUTES

SURVEY FOR: McDonald's Corporation  
10220 N.E. Points Drive  
Kirkland, Washington 98033

LOCATION: Donation Land Claim 42, Northeast 1/4 of  
Section 9, Township 38 South, Range 1 West, WM.  
City of Phoenix, Jackson County, Oregon

PURPOSE: Monument the boundaries of Tax Lots 202 and 205 as  
described in Preliminary Title Reports No. 607215  
& No. 607216 as furnished by American Pacific  
Title & Escrow Company.


PROCEDURE: The descriptions for the two parcels commence at  
the Northwest corner of Donation Land 42, thence  
along the north boundary of the Claim to the  
westerly boundary of the Interstate right of way,  
and then southeasterly to the iron rebars set for  
the right of way. These record calls were held to  
the first found iron rebar. The brass cap  
monument found on the highway centerline control  
was used to control the right of way location,  
using the record State Plane Coordinate bearing of  
the centerline, rotated to true bearing as shown  
on the map.

The 3/4" iron pin from Survey No. 5043 and  
the 5/8" rebar from Survey No. 3461 were used to  
control the right of way location of Fern Valley  
Road.


The location of the southeast corner of that  
parcel described in Instrument No. 79-01290 of the  
Jackson County Deed Records was computed from the  
NW Corner of DLC 42, from which the most southerly  
corner of Tax Lot 202 was then located as required  
by the description.

The easterly boundary of Tax Lot 202, lying  
between Fern Valley Road and Interstate 5, was  
located by record deed call southerly from the  
north boundary of Donation Land Claim 42.

Basis of bearing: Survey No. 5043.



*Roger R. Roberts*



Roger R. Roberts  
Hoffbuhr & Assoc. Inc.