Survey No. 1151

Paul Rynning County Surveyor Medford, Oregon

Subject: Restoration of obliterated corner

Township 37 South, Range 2 West, Willamette Meridian.

Established the East 1/16 corner between Sections 5 and 8. Found the corners of Sections 4, 5, 8, and 9 and the 1/4 corner between Section 5 and 8.

At and equal and proportional distance set an  $1 \frac{1}{4}$  inch iron pipe, 26 inches long, 26 inches in the ground, from which

Black oak, 14 in. in diam., bears N.14°W, 40.5 ft., scribed 301 BT White oak, 9 in. in diam., bears  $S.26\frac{1}{2}$ W., 19.5 ft., scribed 301 BT A 5/8 inch iron pin, bears N.89°25°E., 50 ft. Found a 3/4 inch iron pipe, bears S.46°41°W., 2.65 ft.

At the 1/4 corner between Sections 5 and 8, found a 1 inch gal. pipe, also previously reported by County surveyor, N.1120W., should be, N.110W., 40.4 ft.

