

SURVEY NO. 11528

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

SURVEY FOR: Jacksonville Lodge No. 10
Independent Order of Odd Fellows
Jacksonville, Oregon

LOCATION: Block 7 of Original Plat of Jacksonville
Northwest 1/4 of Section 32, Township 37
South, Range 2 West, W.M., Jackson County,
Oregon.

PURPOSE: Locate and monument the boundaries of the
I.O.O.F. ownership.


PROCEDURE: The boundary of Block 7 was determined by
retracing the street centerline monumentation
around the block. The monument of record at the
intersection of Oregon and California was paved
over and not uncovered for this survey. Its
position was determined by record location from
Survey No. 5131.

The south boundary of the block, being the south
boundary of Lot 8, was interpreted as being parallel
with the north boundary of the block. The lot
boundaries were determined proportionately.


The I.O.O.F. ownership dates back to 1865 (Vol
4, Page 170, Deed Records), and 1873 (Vol 6, Page
516), with both deeds having vague descriptions of
the configuration of the parcels. It was necessary
to trace through the subsequent conveyances in Block
7 to determine the configuration of the remaining
I.O.O.F. ownership.

References were taken to the three street
centerline monuments found under the asphalt, as
shown on the map. The holes were resealed with
asphalt. The descriptions of the references are as
follows:

- [A] = PK nail & shiner 1 ft. above ground in
south face of power pole.
- [B] = "+" in top northeast corner of concrete
planter box.
- [C] = PK nail & shiner 1 ft. above ground in
west face of telephone pole #227.
- [D] = PK nail in middle of sidewalk.
- [E] = PK nail & shiner 2 1/2 ft. above ground
in northwest face of power pole #D7589.
- [F] = "+" in top of east end of 12" dia.
concrete culvert.
- [G] = center bolt in gas valve cover.



Roger R. Roberts



Roger R. Roberts
Hoffbuhr & Assoc., Inc.