

NW cor. DLC 50
Fd. 1-1/2" iron pipe

Survey For
JOHN KENDLE
Located in D.L.C. No. 40,
Sec. 2, T.38S.R.2W., W.M.
By: Mark E. Boyden
Sept. 1958...

So. line J.C.D.R. Vol. 326, Page 67

568.38'

South
573.80'

N. 2° 29' E.

N. 0° 05' 20" E.

SCALE: 1" = 100'

- ⊙ Reestab. Govt. cor.
- Set 5/8" iron pin

W. bdry. D.L.C. No. 40

STAGE

150.58'

N. 76° 08' 20" W

1146.42'

ROAD

SE cor. DLC 40
Fd. 1-1/2" iron pipe

SOUTH

Fd. spike P.I.
at Crooked Creek Rd.



REGISTERED
OREGON
LAND SURVEYOR

Mark E. Boyden
NOVEMBER 4, 1951
MARK E. BOYDEN
281

1157

1157

Survey Narrative to Comply With Paragraph 209.250
Oregon Revised Statutes

SURVEY FOR: John Kendle

PURPOSE: To monument that parcel described in Jackson County Deed Records Volume 443, Page 225, being located in D.L.C. No. 40, Sec. 2, Township 38 South, Range 2 West.

PROCEDURE: Established the centerline of Stage Road South from the P.I. at Crooked Creek Road through the stone P.O.T. located near the East boundary of D.L.C. No. 40 to an intersection of the West boundary of D.L.C. No. 40 on instructions from the county engineer. From this road centerline, intersected the East boundary of D.L.C. No. 40 and ran Northwesterly the deed distance along said road centerline of 1146.42 feet for the point of beginning; thence continued Northwesterly along said road centerline a deed distance of 150.58 feet to establish the Southwest property corner; from these two Southerly property corners, ran Northerly deed record courses to establish the East and Westerly property boundaries. Witness pins were set near the Northerly corners of the property, but no attempt was made to exactly locate the South boundary of that property described in Jackson County Deed Records Volume 326, Page 6.

Set iron pins on the Northerly boundary of Stage Road South as shown, using the solar meridian established on Survey No. 659.

September 1958

