



DETAIL SCALE: 1" = 5'

PLAT OF SURVEY

LOCATED in Donation Land Claim No. 52,
T.36S., R.2W., W.M., Jackson County, Oregon.

May 8, 1989

SURVEYED FOR: *Floyd Venable*
6968 Blackwell Road
Central Point, Oregon 97502

SURVEYED BY: *Edwards Surveying and Land Planning Inc.*
1014 East Pine Street
Central Point, Oregon 97502
Phone: (503) 664-1539

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David A. Edwards

DAVID A. EDWARDS
2339

RECEIVED

Date: 5-9-89 By: *SK*

This survey contains the
- [] Official Map
- [] Legal's Narrative
JACKSON COUNTY
SURVEYOR

LEGEND

- Indicates 5/8" diam. Iron Pin found per R.S.N. 8329 except where noted.
- Indicates 5/8" x 24" steel pin with red plastic cap mkd. "DAVID A. EDWARDS-RPLS 2339" set.
- () Denotes Record Date per R.S.N. 10027 unless otherwise noted.
- x—x—x Fence Line
- R.O.W. = Right of Way
- D.L.C. = Donation Land Claim
- Fd. = Found
- R.S.N. = Recorded Survey Number

SCALE: 1" = 200'

SURVEY NUMBER 11586

Edwards Surveying and Land Planning Inc.
Registered Land Surveyors
1014 East Pine St.
Central Point, Oregon 97502
(503)664-1539

SURVEY NARRATIVE TO COMPLY WITH CHAPTER 209, PARAGRAPH 250,
OREGON REVISED STATUTES

SURVEY FOR: Floyd Venable
6968 Blackwell Road
Central Point, Oregon 97502

LOCATION: In Donation Land Claim No. 52, Township 36
South, Range 2 West, Willamette Meridian,
Jackson County, Oregon.

PURPOSE: To locate and monument a portion of the
Southerly boundary of Tax Lot 2600 for fencing
purposes.

PROCEDURE: Utilized for control those monuments of record
per Recorded Surveys Numbered 3502, 8329 and
10027. The latter survey was tied into and the
record data used to derive a position for the
SE corner of D.L.C. No. 51. The former surveys
were tied into and record data used to compute
a position for the Southerly "2 inch iron pipe"
found on R.S.N. 3502. Computations based on
these methods resulted in the bearings and
distances shown on the accompanying plat.
Monuments set on this survey consist of a 5/8"
x 24" steel pin with a red plastic cap mkd.
"DAVID A. EDWARDS-RPLS 2339".

**BASIS OF
BEARINGS:** Recorded Survey Number 8329.

EQUIPMENT: Nikon NTD-4 Semi-automatic theodolite/E.D.M.

**DATE
COMPLETED:** May 8, 1989

