



C.E. 1/16 COR.  
FD. 3/4" I.R. & B.T.'S  
PER C.S. 4377

SET WITNESS COR.  
TOP OF BANK  
N89°36'34"E 2.50'

N89°36'34"E 1320.66'  
1001.62'

32 33  
2102.73'

1/4 COR.  
FD. C.S. B.C. &  
B.T.'S

∠  
A = 31°03'41"  
E = 19.40'  
R = 511.92'  
T = 142.26'

∠  
A = 89°36'01"  
E = 8.6'  
R = 3046.41'  
T = 229.07'

± 17.8 AC.

R/W  
R = 744.48'  
T = 186.09'

FD. 2" I.P. PER  
DEED RECORD  
B. C.S. 2649

WITNESS  
COR.

FD. CONC. NAIL  
C.S. 2649

FD. 5/8" I.R.  
6" BELOW PAV.  
C.S. 2649

# MAP

SHOWING A SURVEY IN THE SE 1/4 OF  
SEC. 32 AND THE S.W. 1/4 OF SEC. 33, T. 35 S.,  
R. 3W., W.M., JACKSON CO., OREGON

SCALE: 1" = 100'      AUG. 8, 1989

SURVEYED FOR:  
ALETHEIA  
1809 NORTH HIGHWAY 99  
ASHLAND, OREGON

SURVEYED BY:  
MAX H. HULL, SURVEYING  
231 NW "B" STREET  
GRANTS PASS, OREGON

- SET 5/8" X 30" IRON ROD WITH YELLOW PLASTIC CAP MARKED "HULL RS 901"
- FOUND IRON MONUMENTS AS NOTED BASIS OF BEARING SOLAR OBSERVATION SURVEY NARRATIVE SEPARATE DOCUMENT

RECEIVED  
SEP 9 1989  
JACKSON COUNTY  
SURVEYOR

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
MAX H. HULL  
901



Office 476-2425

**MAX H. HULL Land Surveying**

231 N. W. 'B' Street Grants Pass, Oregon 97526

SURVEY NARRATIVE to comply with Paragraph 209.250, O.R.S.

11729

DATE: August 8, 1989

FOR: Aletheia  
1809 North Highway 99  
Ashland, Oregon

PURPOSE: To survey a parcel of land located in the Southeast 1/4 of Section 32 and the Southwest 1/4 of Section 33, Township 35 South, Range 3 West, Willamette Meridian, Jackson County, Oregon.

PROCEDURE: Beginning at the Center East 1/16 Corner at which point I found a 3/4" iron pipe per County Survey 4577 from which I found

A Fir 16" in diam. South  $47^{\circ}30'$  West 32.0 feet blaze healed  
A B. Oak 14" in diam. North  $24^{\circ}30'$  West 16.4 feet blaze healed

Thence I traversed to the East 1/4 Corner at which point I found a 1986 County Surveyor brass cap from which I found

A Cedar 7" in diam. South  $70^{\circ}10'$  East 17.40 feet scribe visible  
A Fir 9" in diam. North  $5^{\circ}$  West 20.80 feet scribe visible

Thence I traversed the apparent center line of the left fork of Sardine Creek Road and the right fork of said road as shown on the map; thence I calculated curves to fit the road center lines as they exist; thence I found and surveyed to monuments per Survey 2649 as indicated on the map; thence I set monuments as indicated and surveyed the North property line and the South property line.

The survey was conducted with a Nikon NTD 4 Total Station.

The survey map is a separate document.

Basis of Bearing is a solar observation.

