



LEGEND

- Indicates monument found per R.S.N. 1784 unless noted otherwise.
- Indicates 5/8" diam. steel pin w/cap mkd. "DW EDWARDS-PLS 74" set.
- () Denotes Deed Record data except where noted.
- x—x—x—x Fence line
- R.S.N. = Recorded Survey Number
- SCALE: 1" = 100'
- BASIS OF BEARINGS: R.S.N. 9449

PLAT OF SURVEY

LOCATED in the NE 1/4 of Section 34, T.37S., R. 1W., W.M.
 Jackson County, Oregon
 October 3, 1989

SURVEYED FOR: *Mike Sasser*
 4360 Barnett Road
 Medford, Oregon 97504

SURVEYED BY: *Edwards Surveying and Land Planning Inc.*
 1014 East Pine Street
 Central Point, Oregon 97502
 Phone: (503) 664-1539

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Paul W. Edwards

OREGON
 JULY 6, 1988
 DARREL W. EDWARDS
 741

RECEIVED
 Date 10-6-89
 This survey consists of
 1 sheet(s) Map
 1 page(s) Narrative
 JACKSON COUNTY
 SURVEYOR

SECTION CORNER
 JACKSON COUNTY BRASS CAP, FOUND

Survey of the NE 1/4 of Sec. 34, T. 37N, R. 1W, S. 4E, Jackson County, Oregon, for the purpose of monumenting the boundaries of said tract.

STATE OF OREGON, COUNTY OF JACKSON, LAND SURVEYOR'S OFFICE, FIELD STATION

CLIENTS: K. W. Basser
 1024 S. W. 1st St.
 Medford, Oregon 97504

LOCATION: In the NE 1/4 of Sec. 34, Township 37 North, Range 1 West of the Willamette Meridian, Jackson County, Oregon.

PURPOSE: To locate and monument the boundaries of that tract described in Document No. 181,031, Official Records for said County and State.

PROCEDURE: The East and South boundaries were monumented according to the above noted deed. The west boundary was determined to be parallel to the East line of Section 34, based upon calls found in the deed recorded as Document Number 73-24706, which describes property west and Southwest of the Basser tract. Monuments set on this survey consist 5/8" x 1 1/2" steel pipe with yellow plastic caps and "DW EDWARDS-PLS 741" attached.

BASIS OF BEARINGS: The North line of the NE 1/4 of Sec. 34, per R.E.N. 9446.

EQUIPMENT: Nikon NTD-4 Semi-automatic theodolite/E.L.C.M.

DATE COMPLETED: October 3, 1989.

**** RECEIVED ****
 Date 10-6-89 By [Signature]
 This survey consists of:
1 sheet(s) Map
1 page(s) Narrative
JACKSON COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR

Darrel W. Edwards

OREGON
 JULY 8, 1908
DARREL W. EDWARDS
 741