

RICHARD G. TEMPLIN
PROFESSIONAL LAND SURVEYOR
2042 Sandra Pl.
Medford, Oregon 97504
(503) 776-0991 • 474-7720

SURVEY NO. 11931

SURVEY FOR: Mr. Fred Gothard
3512 Lone Pine Rd.
Medford, Oregon

Location: Section 16, Township 35 South, Range 2 West,
Willamette Meridian, Jackson County, Oregon.

Purpose: To monument the North One Quarter corner of
Section 16 and the West 1/16 corner of said
Section. Also, to run and mark true line
between the Northeast Section corner of said
Section to the West 1/16 corner.

Date: March 2, 1990

**Basis of
Bearing:** Based upon Solar Observation

Procedure: Utilizing a Wild T-2, Wild T-16 and Mac 1E EDM,
and Red 2L EDM, tied the Northeast and
Northwest Section corners of Section 16.
Computed and ran true line to the position of
the North One Quarter corner. Search of the
original Ives & Hyde corner was made by myself
and the Jackson County Surveyors office,
without results. At the computed proportional
position of the North One Quarter Corner I set:

A 5/8"x30" rebar with yellow plastic cap marked
"TEMPLIN 2359", from which I scribed the
following bearing trees:

A Black Oak, 4" diameter bears S 27° E, 4.10
feet, scribed "1/4 S 16" "BT".
A Madrone, 11" diameter bears S 38° W, 8.75
feet, scribed "1/4S16" "BT".
A Madrone, 12" diameter bears N 77° W, 7.80
feet, scribed "1/4S9 " "BT".
A Madrone, 8" diameter bears N 9° W, 7.20
feet, scribed "1/4S9" "BT".
An unrecorded 5/8" rebar bears S 27° W, 1.40
feet.

11931

RICHARD G. TEMPLIN
PROFESSIONAL LAND SURVEYOR

2042 Sandra Pl.
Medford, Oregon 97504
(503) 776-0991 • 474-7720

I then run N 89°57'51" W, 1331.17 feet to the West 1/16 corner and set:

A 5/8"x30" rebar with yellow plastic cap marked "TEMPLIN 2359", from which I scribed the following bearing trees:

A Douglas Fir, 16" diameter bears N 86 °E, 21.6 feet, scribed " W1/16S9" "BT".
A Ponderosa Pine, 14" diameter bears S 6° E, 15.00 feet, scribed " W1/16S16" "BT".
An unrecorded 5/8" rebar bears N 17° W, 1.07 feet.

