

12042

32 33  
5 4  
T.34S., R.1W.  
T.35S., R.1W.



LEGEND:

- ⊙ = FOUND COUNTY SURVEYOR BRASS CAPPED MONUMENT & ACCESSORIES.
- = FOUND 5/8" IRON PIN W/ PLASTIC CAP MKD. FRIAR PLS 961 PER RS 11855.
- ⊠ = FOUND 5/8" IRON PIN PER RS 5104.
- ⊙ = SET 5/8" x 24" IRON PIN W/ PLASTIC CAP MKD. FRIAR PLS 961.
- ( ) = GOV'T RECORD DATA, UNLESS NOTED.

1329.815'  
(20.00 CH.)  
(1329.96' PER RS 5104.)

(80.00 CH.)

(S00°31'24"E PER RS 5104.)  
S 00°29'21"W 5319.26'

GOV'T LOT 5

MEAN OF THE MEANDERS OF THE LEFT & RIGHT BANKS OF THE ROGUE RIVER PER RS 11855.

0.89' W,  
0.23' S.

N 89°58'50"E 189.52'

N 1/16

S. LINE GOV'T LOT 5

14.52'

N 48°09'10"E

141.46'

155.98'

5 4  
8 9

**SURVEY FOR:**  
JOHN R. McGUIRE  
P.O. BOX 2046  
WHITE CITY, OR 97503

**MAP OF SURVEY**

LOCATED IN THE N.W. 1/4,  
N.W. 1/4 OF S.4, T.35S., R.1W.,  
W.M., JACKSON COUNTY, OR.

SCALE: 1"=50' DATE: MAY 10, 1990

BASIS OF BEARINGS: W. LINE S. 4 PER RS 11855.

**SURVEY BY:**  
L.J. FRIAR & ASSOCIATES, P.C.  
CONSULTING LAND SURVEYORS  
717 W. 10TH, SUITE NO. 1  
MEDFORD, OR 97501

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Larry J. Friar*  
OREGON  
JULY 16, 1971  
LARRY J. FRIAR  
961

\*\* RECEIVED \*\*  
Date 5/21/90 By JK  
This survey consists of:  
1 sheet(s) Map  
1 page(s) Narrative  
JACKSON COUNTY  
SURVEYOR

12042

35 IW 4 T.L.600

Survey No. 12042

Survey Narrative To Comply With O.R.S. 209.250

Survey For: John R. McGuire  
P.O. Box 2046  
Whit City, OR 97503

Location: A portion of the N.W. 1/4 of the N.W. 1/4 of  
Sec. 4, T.35 S., R.1 W., W.W., Jackson County,  
Oregon.

Purpose: To monument the S. line of Gov't Lot 5 as per  
the client's request.

Procedure: Using control established during Survey No. 11855  
by this office, I set the North 1/16 corner common  
to Secs. 4 & 5, and set the intersection of the  
South line of Gov't lot 5 with the mean line of the  
meanders of the left and right banks of the Rogue  
River as established by Survey No. 11855. Those  
monuments found and those set are as shown on the  
attached map.

Basis of Bearing: W. line of Sec. 4 per Survey No. 11855.

Date: May 10, 1990

T35S R1W SEC4 TL600

Larry J. Friar  
L.J. Friar & Associates P.C.  
Consulting Land Surveyors  
717 West 10th, Suite 1  
Medford, OR 97501  
(503) 772-2782

