

SURVEY NO. 12049

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION
TO COMPLY WITH PARAGRAPH 209.130, O.R.S.**

History of original corner establishment:

The original corner point for the quarter corner, sections 4 and 9, Township 36 South, Range 3 East, Willamette Meridian, Jackson County, Oregon, was established by Rufus S. Moore under Contract No. 475 dated July 3, 1883. This corner was remonumented from original evidence by the Bureau of Land Management Group 350 (J.Gawron) in 1962. Surveyor Gawron set a standard Bureau of Land Management Monument marked:

**BUREAU OF LAND MANAGEMENT
T 36 S R 3 E**

S4
1/4 ———
S9
1962

CADASTRAL SURVEYS

Description of corner evidence found:

At the corner point, I found the iron post set by Gawron in good condition, and the following accessories:

An 11" diameter fir bears N.81°16'W., 6.1 feet distance, with a healed blaze.

An 8" diameter fir, bears S.79°18'E., 6.5 feet distance, with a healed blaze.
This tree is now dead.

**Description of accessories I established to perpetuate
the original location of this corner:**

An 8" diameter fir bears S 40°21'W., 25.0 feet distance, scribed 1/4 S9LS1071 BT.

A 9" diameter fir bears N.46°45'E., 51.8 feet distance, scribed 1/4 S4LS1071 BT.

A 6" diameter fir bears S.6°34'E., 15.6 feet distance, scribed 1/4 S9LS1071 BT.

Basis of Bearing
Solar Observation

Date
May 2, 1990

**HAROLD L. CENTER
REGISTERED PROFESSIONAL LAND SURVEYOR
OREGON CERTIFICATE NO. 1071**

