



survey Narrative to Comply with Paragraph 209.250,  
Oregon Revised Statutes

For:

C.W. and Dorothy Spencer

Purpose:

To locate the boundaries of an area, designated by Mr. Spencer. Area to have 450.0' frontage on Rogue River Drive and bound on the South by a break in the terrain and to extend to his previous West boundary.

Procedure:

I made the Survey on Mr. Spencer's land lying to the East of this area. From my previous survey I had control points to establish the East line of this area, also the Right of way of Rogue River Drive. The N.E. Corner had been previously established by an intersection of a line from the 1/4 5/8 through the N.W. Corner of Government Lot 4 Section 5 to the Rogue River Drive Right of Way. From this corner I extended the road R/W 450.0 ft. and set the S.W. corner. From this corner I ran a line to an intersection with the line produced through the N.W. Corner of Government Lot 4, and set the S.E. Corner of this area. This line established the closure of the three sided area.

One-half inch iron pipe was used to mark the S.W. and S.E. Corners.

