

Paul Rynning, County Surveyor
Jackson County Court House
Medford, Oregon

SUBJECT: Re-establishment of corners. T395R1E

/ S.S.W. D.L.C. 55;

Found dead 20" white oak with scribe visible, bears, S.42°E., 40.92 ft.
Found stump hole of Black Oak, N.78°W., 39.9 ft.
Found stone 6 x 6 x ?, N.42°W., 0.92 ft.
A white oak 24", bears S.6°W., 21.8 ft. scribed 301
A white oak 9 ins., bears N.49°W., 52.25 ft., scribed 301.
A white oak, 14 ins., bears N.6°E., 1.00 ft., scribed 301.

S.S.E., D.L.C. 54; Set a 5/8 in. pin near top of irrigation bank.

Found a 20" white oak, N.44°W., 81.84 ft. partial scribe visible.
Found stump hole, N.27°E., 51.14 ft.
A white oak, 5 ins. diam., 2 blazes, bears N.73°W., 69.4 ft.
A white oak, 8 ins. diam., bears S.23°W., 38.2 ft.

/ W.S.W., D.L.C. 55; Found a stone in place, in rock md., 12" x 12" x 4".

Found original bearing tree, a black oak 26 ins. diam., S.45°E., 40.26 ft.
Found orig. bearing tree, stump and old blaze, N.22°E., 116.5 ft.
A white oak, 14 ins. diam., 2 blaze, N.9½°W., 93.3 ft.
A white oak, 8 ins. diam., 2 blaze, S.22½°W., 51.3 ft.
~~True corner location bears 1.12 ft. east on the east boundary of D.L.C. 54.~~

N.W., D.L.C. 55; A granite stone, 5 x 6 x 12 ins. in place with cross at fence corner, from which

An apple tree, 12 ins. diam., bears southerly, 8.6 ft.
An apple tree, 16 ins. diam., bears East 66.3 ft.

N.W. cor. D.L.C. 59; Set a 1½ in. pipe, 26 in. long, 6 in. below the surface.

Found remains of original bearing tree, a black oak, N.33°E., 66.66 ft.
Found an 18 in. alder,, S.68½°E., 88.7 ft., scribed C S B T, approx.
10 years ago.
Found a 40 in. black oak stump, N.25°E., 124.4 ft., scribed C S B T,
approx. 10 years ago.
Found a 1½ in. pipe, 2 ft. north of east-west, South 2° 25' West, 11.90ft
A power pole - E - 581, N.88°W., 218.1 ft.

N.E. cor. D.L.C. 55; Found a sand stone 3 x 6 x 12 ins. above the ground
scribed C 56, north face and C55, on the south face.

Found, also a stump hole, N.10°E., 19.0 ft.
Found, also a stump hole, S.64°W., 34.98 ft.
A white oak, 18 ins. diam., bears N.13½°E., 44.8 ft. scribed 301 B T.
A white oak, 12 ins. diam., bears N.79°E., 20.8 ft. scribed 301 B T.
A white oak, 9 ins. diam., bears N.79°W., 17.8 ft. scribed 301 B T.

S.E. cor. D.L.C. 56; Set a $1\frac{1}{2}$ in. pipe, 26 in. long, 28 ins. in the ground. The original B T, to the NW was shown to me by a local resident, of many years, and now being a sunken hole in the earth. The exact center, after considerable digging, was undetermined. Held record distance from original B T distance and a course East from the North-east corner of D.L.C. 55 from which

A white oak, 4 ins. diam., bears S.2°W., 65.6 ft., scribed 301 B T.

A black oak, 4 ins. diam., bears N.42°E., 121.7 ft. scribed 301 B T.

A power pole No. E-582, N.35 $\frac{1}{4}$ °E., 67.4 ft.

A sand stone gate post, 5 ft. high, 12 x 12 ins., a - V- near the base at the N.E. cor. of, bears S.29 $\frac{1}{4}$ °W., 7.85 ft.



Edward A. McGinty

