

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

TO COMPLY WITH PARAGRAPH 209.130
OREGON REVISED STATUTES

History of Original Establishment:

The original subdivision of Township 32 South, Range 3 East, Willamette Meridian, Jackson County, Oregon was surveyed by Rufus S. Moore under Contract No. 496 dated 3/03/1884 and approved 6/17/1884. This corner was re-established by C.Z. Boyden on October 31, 1951, and remonumented by the Bureau of Land Management in 1962.

Description of corner evidence found:

The one-quarter corner for sections 20 and 29, Township 32 South, Range 3 East.

At the corner point, I found a 3-inch diameter Bureau of Land Management monument protruding 6 inches above ground, with 1 1/2" diameter iron pipe protruding 14" alongside. Cap marked:

UNITED STATES DEPARTMENT OF INTERIOR
UNLAWFUL TO DISTURB

S 20
1/4 ———
S 29

-1962-
CADASTRAL SURVEYS
BUREAU OF LAND MANAGEMENT

And the following accessories:

A 9-inch diameter fir bears N.45°14'W., 16.80 feet distance, with a healed blaze. (Record: N.45°00'W., 25 links (16.50 feet)).

A 38-inch diameter pine stump bears S.14°47'E., 13.20 feet distance, with fragmentary scribing visible. (Record: S.50°00'E., 18 links (11.88 feet)).

An 8-inch diameter fir bears S.09°47'W., 16.30 feet distance, with a healed blaze. This tree is now dead. (Record: S.10°00'W., 24.5 links (16.17 feet)).

Description of monument and accessories I establish to perpetuate the original location of this corner:

I marked the following new accessory:

A 12-inch diameter fir bears S.59°26'W., 23.80 feet distance, scribed 1/4S29LS1071 BT.

Basis of Bearing: Solar Observation

December 17, 1990

HAROLD L. CENTER
REGISTERED PROFESSIONAL LAND SURVEYOR
OREGON CERTIFICATE NO. 1071

