

12391



The purpose of this survey was to establish the lost position for the S1/4 Cor. Sec.36 and to establish the south line of Sec.36 for land management purposes. Survey procedures followed, corners and bearing trees established by this survey are in accordance with the U.S.D.I. Manual of Instructions.

SW Sec.36
1975 Jackson County
Brass Cap

Distances from BT's established are from nails in lower face.

Basis of Bearings: G.L.O. Record

By Single Proportion:
Set 5/8"x30" Rebar
with 2" Surv. Cap w/BT's
9" D. fir, N28°W, 19.21'
6" Oak, S18°E, 45.49'

Legend

- Found Corner
- Set Corner

— Lines run this survey to delineate Weyerhaeuser ownership for land management purposes.

(1) G.L.O. Record

T40S
S36
W1/16 R4E
S1
T41S
ORLS 139
1990

By Single Proportion:
Set 2"x30" Galv. Iron Pipe
with 2 1/2" Brass Cap w/BT's
8" D. fir, N85°W, 31.03'
7" Cedar, N0°E, 38.97'
7" W. fr, S50°E, 15.25'
14" P. pine, S18°W, 32.34'

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Dennis L. Brandt
OREGON
SEPT. 23, 1977
DENNIS L. BRANDT
1139

S90° 00' 00"E
5350.745'
(80ch)

T40S
S36
V4 R4E
S1
T41S
ORLS 139
1990

By Single Proportion:
Set 5/8"x30" Rebar
with 2" Surv. Cap w/BT's
11" D. fir, N67°W, 27.90'
6" W. fir, S26°E, 6.50'

** RECEIVED **
Date 1-29-91 By *DF*
This survey consists of:
1 sheet(s) Map
2 page(s) Narrative
JACKSON COUNTY
SURVEYOR

T40S
S36
E1/16 R4E
S1
T41S
ORLS 139
1990

SE Sec.36
1974 BLM
Brass Cap

MAP OF SURVEY LOCATED IN
SEC.36, T.40S., R.4E., W.M.,
JACKSON COUNTY, OR



Weyerhaeuser Company
Klamath Falls

Scale: 1"=600' Date: December, 1990

Survey: Barnett Del.: Brandt

12391