

Survey No. 1253

Paul Rynning  
County Surveyor  
Medford, Oregon  
June 8, 1959

Subject: Re-establishment of Section Corner

Township 38 South, Range 2 West, Willamette Meridian

Section corner 17, 18, 19, and 20

Found 4" x 4" oak stake from which I found

16" Black Oak N.21°E., 44.88 ft.,

scribe rotted away

Stump and downed snag with 2 blazes bears S.78°E., 35.64 ft.

Stump hole and downed snag with old blaze bears S.14°W., 61.38 ft.

Stump and downed snag N.69°W., 29.04 ft.

From the above evidence set a 3/4" pipe 26" long and 22" in ground from which

a 16" Black Oak bears N.21°E., 44.88 ft., original tree

Scribed 16" Black Oak 301 B T, S.24°E., 35.00 ft.

Scribed 5" White Oak 301 B T, S.62°W., 17.85 ft.

Scribed 9" Black Oak 301 B T, N.6½°W., 36.1 ft.

Var. 19½°

¼ Corner, Section 17 and 18, Found 4" x 6" Oak Stake scribed ¼°S. on North and South face, approximately 20 to 30 years old also found a 20" Fir N.57°E., 12.5 ft. Scribed ¼, approximately 60 to 70 years ago, neither of the two original trees where found, this being the accepted corner for many years. I removed stake and set a 1½" x ½" Iron bar 30" long and 24" in ground. From which

the above 16" Fir bear N.57°E., 12.5 ft.

Scribed a 9" laurel 301 B T, bears S.76°W., 23.35 ft.

Var. 19½°



*Edward A. McGinty*

