

12715

SURVEY PLAT AND NARRATIVE TO COMPLY WITH  
PARAGRAPH 209.250, OREGON REVISED STATUTES

SURVEY SITUATE IN THE SW 1/4 OF  
SEC. 26, T. 38 S., R. 3 W., W.M.,  
JACKSON COUNTY, OREGON

SURVEY FOR: Dollie A. Kitchen  
700 Buttereup Lane  
Jacksonville, OR 97530

SURVEY BY: Charles H. Hurst  
765 Sunrise Avenue  
Medford, OR 97504

PURPOSE: To set the SW corner of client's property  
and locate the unrecorded survey monument  
near the NW corner thereof showing the  
relationship of fence lines in the  
immediate vicinity.

PROCEDURE: Electronic distance measurements-random line traverse.

BEARINGS: Based on LHA solar observation.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Charles H. Hurst*

OREGON  
OCTOBER 30, 1959  
CHARLES H. HURST  
483

October 16, 1991

\*\* RECEIVED \*\*

Date 11-1-91 By BF

This survey Consists of:

1 sheet(s) Map

0 page(s) Narrative

JACKSON COUNTY  
SURVEYOR

PROJECTED GW SW 1/64  
COR.



W 1/2 SW 1/4 SW 1/4  
POR. OF O.R. 83-12298

27  
34

FD. SEC. COR.  
1987 C.S. BR. CAP/  
PIPE MON.

561.08'

W-W 1/64 COR. - SET 3/4" X 30" IRON PIN/PLASTIC CAP MKD. HURST LS 483

FROM WHICH: A 11" DIA. D. FIR BR. N 15 1/2° E 15.8' TO CTR. MKD. WW 1/64 S 26 BT"  
A 9 1/2" DIA. D. FIR BR. S 20 1/2° W 5.5' TO CTR. MKD. WW 1/64 S 35 BT"  
A 12" BRIDGE SPIKE BR. S 64° 52' 02" E 51.83'  
AN 3/8" FC. COR. BR. N 80 3/4° E 70.8'  
A 5/8" IRON PIN BR. N 2° 02' 31" E 1337.94'

1983.24'

E 1/2 SW 1/4 SW 1/4  
POR. OF O.R. 83-20267 & 83-06187

FD. 5/8" IRON PIN  
REPORTEDLY SET  
BY HUGH INGLE IN  
1971 FOR BERT HAAR

LEGEND  
- X - EXISTING FENCE LINE

SCALE: 1" = 50'

1987 C.S. BR. CAP/PIPE  
MON.

26  
35

MEAS. S 88° 25' 38" E 2644.32'  
GOV'T. REG. (APPV. JAN. 13, 1912) = S 88° 10' E 2640'

38-3W-26 T.L. 412

12715