



**\*\* RECEIVED \*\***

Date: 12-30-91 By: *George Burrell*

This survey consists of:  
 1 sheet's map  
 1 page(s) Narrative

JACKSON COUNTY SURVEYOR

REGISTERED  
**PROFESSIONAL LAND SURVEYOR**  
*George Burrell*  
 OREGON  
 JULY 10, 1984  
 GEORGE R. BURRELL  
 P.L.S.

**MAP OF SURVEY**

Of Lot Line adjustment (Co. File No. 91-99-LLA). Located in the N.W. 1/4 of Section 3, Twp. 40S, R3E W.M.

For: SHARON WIESNER  
 By: George Burrell, P.L.S., 1379 Brookdale, Medford, OR 97504  
 Nov. 19, 1991  
 Rev. Dec. 6, 1991

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR:

Sharon Wiesner  
11475 Hwy. 66  
Ashland, OR 97520

LOCATION:

The Northwest 1/4 of Section 3, Township 40 South, Range 3 East

PURPOSE:

To adjust, monument and describe tax lots no. 703, 704 and 800 according to Jackson County Department of Planning approval of same and the clients instructions.

PROCEDURE:

The East boundary of unadjusted tax lot no. 704 was located according to the found monuments of recorded surveys no. 7446 and 8963. The North boundary was established according to deed record.

The right of way of Highway No. 66 was located from the average centerline of the existing a.c. pavement. The Easterly right of way of the Hyatt Lake Timber Access Road was established at deed record bearing and distance from the Northwest corner of section 3.

The adjusted tax lot boundaries were located according to County approval and the clients instructions.

BY:

George Burrell, P.L.S.  
1379 Brookdale Rd.  
Medford, Oregon 97504  
Dec. 6, 1991

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*George Burrell*

OREGON  
JULY 10, 1964  
GEORGE R. BURRELL  
638

