
S2 T35S R3E W.M.



CERTIFICATE OF SURVEY

I, ARTHUR R. RAMBO, REGISTRATION No. 1086 REGISTERED PROFESSIONAL LAND SURVEYOR STATE OF OREGON, HEREBY CERTIFY THAT THIS MAP CORRECTLY REPRESENTS A SURVEY MADE BY ME OR UNDER MY DIRECTION IN CONFORMANCE WITH THE LAWS OF THE STATE OF OREGON RECIOTERED

anthor R. Rambo

- FOUND STANDARD B.L.M. MONUMENT
- FOUND MONUMENT SET SURVEY No. 6077
- SET 5/8" BY 30" REBAR WITH 2" ALUM. CAP
- 1855 GOVERNMENT RECORD
- G.R. 2 1883 GOVERNMENT RECORD
- GROUP No. 935 GOVERNMENT RECORD
- PRIVATE SURVEY No. 6077
- P. S. 2 PRIVATE SURVEY No. 10,121 LINE POSTED AND BLAZED THIS SURVEY

SCALE

BASIS OF BEARING

SURVEY No. 10,121

I" = 500'

SURVEY FOR

MEDFORD CORPORATION

MEDFORD, OREGON 97501

LOCATION:

WEST HALF OF SECTION 2 TOWNSHIP 35 SOUTH RANGE 3 EAST WILLAMETTE MERIDIAN, JACKSON COUNTY, OREGON.

SURVEY FOR'S

MEDFORD CORPORATION

P.O. BOX 550

MEDFORD, OREGON 97501

SURVEY BY:

ARTHUR R. RAMBO

LS 1086

735 VISTA PARK DRIVE

EAGLE POINT, OREGON 97524

DATE:

DECEMBER 5, 1991

BASIS OF BEARING: SURVEY #10121 (WEST HALF NORTH LINE OF SECTION 2)

PURPOSE:

TO MARK AND POST MEDFORD CORPORATION LAND IN THE WEST HALF OF SAID SECTION 2.

PROCEDURE:

THE ORIGINAL SURVEY OF SECTION 2 WAS COMPLETED BY NATHANIEL FORD UNDER CONTRACT NUMBER 58 DATED APRIL 15, 1855. RUFUS MOORE COMPLETED A RETRACEMENT OF THE NORTH LINE UNDER CONTRACT NUMBER 475 DATED JULY 3, 1883. THE SOUTH 1/4 CORNER OF SECTION 2 HAD BEEN RÉ-ESTABLISHED BY PROPORTIONATE MEASURE ON SURVEY #6077. THE SOUTHWEST CORNER AND THE EAST 1/4 CORNER WERE REMONUMENTED IN 1962, BY THE BUREAU OF LAND MANAGEMENT. THE NORTHWEST CORNER AND THE NORTH 1/4 CORNER WERE REMONUMENTED IN 1964, BY THE BUREAU OF LAND MANAGEMENT. THE WEST 1/4 CORNER WAS REMONUMENTED AND THE NORTH AND SOUTH 1/16 CORNERS COMMON TO SECTION 2 AND 3 WERE ESTABLISHED IN 1977, BY THE BUREAU OF MANAGEMENT. I RAN CLOSED LOOP TRAVERSES TYING TO THE CORNERS NEEDED TO SUBDIVIDE THE WEST HALF OF SECTION 4. I THEN CALCULATED THE SUBDIVISION OF THE WEST HALF OF SECTION 4. THEN , I RAN THE INTERIOR LINES AND SET THE CORNERS NEEDED FOR THIS SURVEY AS SHOWN ON THE PLAT TO ACCOMPANY THIS NARRATIVE.

CORNERS FOUND AND ACCEPTED FOR CONTROL:

ALL MEASUREMENTS TO BEARING TREES ARE TO THE CENTER OF TREE AT THE BASE UNLESS OTHERWISE STATED.

SECTION CORNER COMMON TO SECTIONS 34 AND 35, TOWNSHIP 34 SOUTH RANGE 3 EAST, AND SECTIONS 2 AND 3, TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I FOUND A STANDARD BUREAU OF LAND MANAGEMENT MONUMENT WITH A 91/2 INCH BY 6 INCH BY 10 INCH STONE AGAINST EAST SIDE OF MONUMENT WITH 4 NOTCHES ON WEST AND 2 NOTCHES ON EAST SIDE OF STONE, MONUMENT MARKED:

> T348 R3E 834 835

S3 S2 T358 1964

AGE 2

FROM WHICH:

A 12 INCH DIAMETER FIR BEARS N64° 26'E 29.0 FEET WITH AN UNOPENED FACE.
A 10 1/2 INCH DIAMETER PINE BEARS N72° 34'E 28.0 FEET MARKED 34S R3E S35.
A 9 INCH DIAMETER FIR BEARS S52° 39'E 18.0 FEET WITH AN UNOPENED FA.E.
A 49 INCH DIAMETER CEDAR STUMP BEARS S52 39'E 61.8 FEET WITH AN UNOPENED FACE. A 26 INCH DIAMETER PINE BEARS S12 47'W 21.9 FEET WITH TWO UNOPENED FACES. A 24 INCH DIAMETER FIR BEARS N59 02'W 24.6 FEET WITH AN UNOPENED FACE.

ONE-QUARTER CORNER COMMON TO SECTION 35 TOWNSHIP 34 SOUTH RANGE 3 EAST. RANGE 3 EAST, AND SECTION 2 TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I FOUND A STANDARD BUREAU OF LAND MANAGEMENT MONUMENT EXPOSED 10 INCHES, WITH A 17 INCH BY 5 1/2 INCH BY 5 1/2 MONUMENT EXPOSED 10 INCHES, WITH A 17 INCH BY 5 1/2 INCH BY 5 1/2 INCH STONE WITH 1/4 MARKED ON NORTH SIDE OF STONE AGAINST SOUTH SIDE OF MONUMENT, MONUMENT MARKED:

T34S R3E 1 <u>535</u> 4 52 T35S 1964

FROM WHICH:

A 15 1/2 INCH DIAMETER FIR BEARS S84 34'W 65.6 FEET WITH AN UNOPENED FACE.
A 12 INCH DIAMETER FIR BEARS N16 07'E 47.0 FEET WITH AN UNOPENED FACE.

ONE-QUARTER CORNER COMMON TO SECTION 1 AND 2 TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I FOUND A STANDARD BUREAU OF LAND MANAGEMENT MONUMENT, EXPOSED 9 INCHES, MONUMENT MARKED:

T35S R3E 1/4 S2 S1 1962

FROM WHICH:

A 17 INCH DIAMETER FIR STUB BEARS N72°25'W 49.5 FEET WITH AN UNOPENED FACE.
A 24 INCH DIAMETER FIR BEARS S55° 31'E 32.0 FEET WITH AN UNOPENED FACE.
A 37 1/2 INCH DIAMETER FIR SNAG BEARS S32° 10'E 36.1 FEET WITH SCRIBES VISIBLE IN A PARTIALLY OPENED FACE.

ONE-QUARTER CORNER COMMON TO SECTION 2 AND 11 TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I FOUND A 1 1/4 INCH DIAMETER ALUM. CAP ON A 5/8 INCH DIAMETER REBAR EXPOSED INCHES, MONUMENT MARKED:

RE 4186

<u>\$2</u> \$11

FROM WHICH:

A 9 INCH DIAMETER PINE BEARS S45 U0'E 20.8 FEET MARKED RE 4186 BT.
A 16 INCH DIAMETER CEDAR BEARS N54 30'W 63.9 FEET MARKED RE 4186 BT.

SECTION CORNER COMMON TO SECTION 2,3,10, AND 11 TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I FOUND A STANDARD BUREAU OF LAND MANAGEMENT MONUMENT, IN A MOUND OF STONE, EXPOSED 8 INCHES, MONUMENT MARKED:

PAGE 3

R3E T355 52 53

> 511 S10 1962

FROM WHICH:

A 2 INCH DIAMETER IRON PIPE BEARS SOUTHEAST 0.25 FEET -52 S3 MARKED

MEDCO

A 7 1/2 INCH DIAMETER FIR BEARS S57° 07'E 22.5 FEET A 22 1/2 INCH DIAMETER FIR BEARS \$43° 56'E 23.4 FEET WITH AN UNOPENED FACE. A ROTTED FIR STUMP BEARS S48° 15 W 6.4 FEET WITH A WITH HEALED FACES. ROTTED FIR LAYING ALONGSIDE FACE UNOPENED. A 28 1/2 INCH DIAMETER FIR BEARS S43° 38'W 29.0 FEET A 23 INCH DIAMETER FIR STUMP BEARS N33° 32'W 29.5 FEET WITH AN UNOPENED FACE. A 10 1/2 INCH DIAMETER FIR BEARS N10° 30'W 18.4 FEET WITH AN UNOPENED FACE.

AN 18 INCH DIAMETER FIR BEARS N42° 27'E 28.3 FEET WITH AN UNOPENED FACE.

SOUTH ONE-SIXTEENTH CORNER COMMON TO SECTION 2 AND 3 TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I FOUND A STANDARD BUREAU OF LAND MANAGEMENT MONUMENT, EXPOSED 7 INCHES, MONUMENT MARKED:

5 1/16

S2 53

1977

FROM WHICH:

A 19 INCH DIAMETER FIR BEARS N31° 04'W 12.0 FEET A 16 1/2 INCH DIAMETER FIR BEARS N68° 52'E 21.7 FEET WITH AN UNOPENED FACE. WITH AN UNOPENED FACE.

ONE-QUARTER CORNER COMMON TO SECTION 2 AND 3 TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I FOUND A STANDARD BUREAU OF LAND MANAGEMENT MONUMENT, IN A MOUND OF STONE, EXPOSED 8 INCHES, MONUMENT MARKED: R3£ T355

1/4 52 53 1977

FROM WHICH:

A 23 INCH DIAMETER FIR STUMP BEARS 539° 57'W 53.9 FEET A 39 INCH DIAMETER PINE STUMP BEARS \$55° 03'W 36.6 FEET WITH AN UNOPENED FACE. WITH NO MARKS VISIBLE ON A PARTIALLY OPENED FACE. A 12 1/2 INCH DIAMETER FIR BEARS N89° 53'E 6.1 FEET A 38 INCH DIAMETER ROTTEN CEDAR STUMP BEARS S70° 57'E 21.6

NORTH ONE-SIXTEENTH CORNER COMMON TO SECTION 2 AND 3 TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I FOUND A STANDARD BUREAU OF LAND MANAGEMENT MONUMENT, IN A MOUND OF STONE, EXPOSED 8 INCHES, MONUMENT MARKED:

N 1/16

S2 53

DAGE 4

FROM WHICH:

AN 18 INCH DIAMETER FIR BEARS N36° 58'W 77.6 FEET WITH AN UNOPENED FACE. A 22 INCH DIAMETER FIR BEARS S55° 27'E 22.7 FEET WITH AN UNOPENED FACE.

CORNERS SET THIS SUMVEY

ALL MEASUREMENTS TO TREES ARE TO THE CENTER AT BASE UNLESS OTHERWISE STATED. BEARING TREES HAVE A BRASS WASHER, MARKED LS 1086, NAILED TO LOWER FACE OF TREE.

CENTER WEST ONE-SIXTEENTH CORNER SECTION 2 TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I SET A 5/8 BY 30 INCH REBAR WITH A 2 INCH DIAMETER ALUMINUM CAP, IN A MOUND OF STONE, EXPOSED 8 INCHES, MONUMENT MARKED:

T35S R3E S 2 CW . 1/16

LS 1086

FROM WHICH:

A 7 1/2 INCH DIAMETER FIR BEARS N71° 24'W 26.1 FEET MARKED CW 1/16 S2 IN UPPER FACE, BT IN LOWER FACE. AN 8 INCH DIAMETER FIR BEARS S29° 03'W 15.0 FLET MARKED CW 1/16 S2 IN UPPER FACE, BT IN LOWER FACE.

NORTH WEST ONE-SIXTEENTH CORNER SECTION 2 TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I SET A 5/8 BY 30 INCH REBAR WITH A 2 INCH DIAMETER ALUMINUM CAP, IN A MOUND OF STONE, EXPOSED 7 INCHES, MONUMENT MARKED:

T35S R3E S 2 NW . 1/16

LS 1086

FROM WHICH:

A 7 1/2 INCH DIAMETER FIR BEARS N53° 17'W 18.0 FEET MARKED NW 1/16 S2 IN UPPER FACE, BT IN LOWER FACE. A 9 INCH DIAMETER FIR BEARS S7° 01'W 19.6 FEET MARKED NW 1/16 S2 IN UPPER FACE, BT IN LOWER FACE.

CENTER NORTH ONE-SIXTEENTH CORNER SECTION 2 TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I SET A 5/8 BY 30 INCH REBAR WITH A 2 INCH DIAMETER ALUMINUM CAP, EXPOSED 9 INCHES, MONUMENT MARKED:

T35S R3E S 2 CN . 1/16

LS 1086

FROM WHICH:

A 5 1/2 INCH DIAMETER FIR BEARS \$41° 42'W 10.9 FEET MARKED ON 1/16 \$2 IN UPPER FACE, BT IN LOWER FACE. A 9 1/2 INCH DIAMETER FIR BEARS \$61° 18'E 6.9 FEET MARKED ON 1/16 \$2 IN UPPER FACE, BT IN LOWER FACE.

CENTER ONE-QUARTER CORNER SECTION 2 TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I SET A 5/8 BY 30 INCH REBAR, IN A MOUND OF STONE, EXPOSED 8 INCHES, MONUMENT MARKED:

T355 R3E S 2 C . 1/4

LS 1086

THE PROPERTY OF THE PROPERTY O

PAGE 5

FROM WHICH:

AN 8 1/2 INCH DIAMETER FIR BEARS S85° 25'E 8.5 FEET MARKED C 1/4 S2 IN UPPER FACE, BT IN LOWER FACE. A 4 1/2 INCH DIAMETER FIR BEARS S6° 42'W 19.1 FEET MARKED C 1/4 S2 IN UPPER FACE, BT IN LOWER FACE. AN 11 INCH DIAMETER FIR BEARS N7° 37'E 21.7 FEET MARKED C 1/4 S2 IN UPPER FACE, BT IN LOWER FACE. A 9 1/2 INCH DIAMETER FIR BEARS N25° 03'W 185.9 FEET MARKED C 1/4 S2 IN UPPER FACE, BT IN LOWER FACE.

CENTER SOUTH ONE-SIXTEENTH CORNER SECTION 2 TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I SET A 5/8 BY 30 INCH DIAMETER REBAR, WITH A 2 INCH DIAMETER ALUMINUM CAP, EXPOSED 7 INCHES, MONUMENT MARKED:

T35S R3E S 2 CS . 1/16

LS 1086

FROM WHICH:

A 7 1/2 INCH DIAMETER FIR BEARS N34° 50'W 32.8 FEET MARKED CS 1/16 S2 IN UPPER FACE, BT IN LOWER FACE. A 5 1/2 INCH DIAMETER FIR BEARS S80° 18'E 20.8 FEET MARKED CS 1/16 S2 IN UPPER FACE, BT IN LOWER FACE.

SOUTH WEST ONE-SIXTEENTH CORNER SECTION 2 TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I SE A 5/8 BY 30 INCH REBAR, WITH A 2 INCH DIAMETER ALUMINUM CAP. EXPOSED 8 INCHES, MONUMENT MARKED:

T35S R3E S 2 SW . 1/16

LS 1086

FROM WHICH:

A 9 1/2 INCH DIAMETER FIR N61° 41'E 23.7 FEET MARKED SW 1/16 S2 IN UPPER FACE, BT IN LOWER FACE. A 10 INCH DIAMETER FIR BEARS N15° 37'W 14.5 FEET MARKED SW 1/16 S2 IN UPPER FACE, BT IN LOWER FACE.

WEST ONE-SIXTEENTH CORNER COMMON TO SECTION 2 AND 11 TOWNSHIP 35 SOUTH RANGE 3 EAST. AT THE CORNER LOCATION I SET A 5/8 BY 30 INCH REBAR, WITH A 2 INCH DIAMETER ALUMINUM CAP, IN A MOUND OF STONE, EXPOSED 7 INCHES, MONUMENT MARKED:

T35S R3E S 2 W _ 1/16 S 11

LS 1086

FROM WHICH:

A 6 1/2 INCH DIAMETER OAK BEARS S70° 16'E 25.4 FEET MARKED W 1/16 S11 IN UPPER FACE, BT IN LOWER FACE. A 5 INCH DIAMETER FIR BEARS N11° 24'W 59.8 FEET MARKED W 1/16 S2 IN UPPER FACE, GT IN LOWER FACE.

