



- LEGEND**
- FD. 5/8" IRON ROD WITH YELLOW PLASTIC CAP MARKED "TEMPLIN LS 2359", PER R.S. 12679
 - FD. 5/8" IRON ROD PER R.S. 7754, 7960
 - ⊙ FD. BRASS CAP WITNESS CORNER PER RS 5607.
 - SECTION CORNER POSITION PER R.S. 7960 (CORNER NOT TIED THIS SURVEY)
 - SET 5/8" x 30" REBAR WITH YELLOW PLASTIC CAP MARKED "TEMPLIN LS2359"
 - () RECORD BEARING/DISTANCE PER R.S. 12679
 - [] RECORD BEARING/DISTANCE PER R.S. 7960
- BEARINGS BASED UPON R.S. 12679

SCALE: 1"=40'

36 - 4W - 20D - TL 3500

20 21
29 28

RECEIVED
Date 5-26-92 by BP
This document consists of:
1
1
JACKSON COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR
M J Templin
RICHARD G. TEMPLIN
7359

RICHARD TEMPLIN LAND SURVEYING
2042 SANDRA PL 776-0991 & 474-7720 MEDFORD, OREGON
MAP OF SURVEY
LOCATED IN
NE 1/4 OF SE 1/4 OF SEC. 20, T.36S., R.4W., W.M.
JACKSON COUNTY, OREGON
SURVEYED FOR: CLAUDIA BROWNE 777 NE 7TH STREET GRANTS PASS, OREGON
DATE: MAY 7, 1992

RICHARD G. TEMPLIN
PROFESSIONAL LAND SURVEYOR

2042 Sandra Pl.
Medford, Oregon 97504
(503) 776-0991 • 474-7720

NARRATIVE

Survey No. 13014

SURVEY FOR: Claudia Browne
777 NE 7th Street
Grants Pass, Oregon 97526

LOCATION: NE 1/4 of the SE 1/4 of Section 20, Township 36
South, Range 4 West, of the Willamette Meridian,
Jackson County, Oregon.

PURPOSE: To survey and mark the East line of Tax Lot 3500.

DATE: May 7, 1992

BASIS OF BEARING: Bearings based upon Recorded Survey
number 12679.

PROCEDURE: The as-constructed centerline of Pacific Highway
Number 99 was used for locating the approximate
South right of way line. From previously set
control points computed the point of intersection
of said South right of way line of Pacific
Highway Number 99 and the East line of Section
20. At set point set a 5/8" rebar, as shown and
flagged said East line with Flo-red ribbon.

