

13082

Proportioned Corner Book 50, page 52

PROPORTIONED SECTION CORNER COMMON TO SECTIONS 25, 30, 31,
AND 36, TOWNSHIP 37 SOUTH, RANGE 4 WEST AND RANGE 5 WEST,
WILLAMETTE MERIDIAN, JOSEPHINE COUNTY, OREGON.

Found 1" iron pipe with plastic cap marked "Jackson C.S." per CS
Book 8, page 9, 5 inches below surface. From which bearing tree
per CS 137-68:

A White Oak, 37" in diameter, bears N 62° 04' W, with face
healed over.


1/2 inch iron pin bears S 0° 02' E, 387.92 ft.,
(SE Corner DLC 39)

From which bearing objects per CS Bk. 8, page 9:

A 5/8" iron rod bears N 5° 47' 35'' E, 240.42 ft. with
plastic cap marked "Jackson C.S.". Pin is 1 ft. south of
6x8x5 ft. high concrete structure.

A 5/8" iron rod bears S 89° 38' 19" E, 247.75 ft., with
plastic cap marked "Jackson C.S.". Pin is S 60° E, 17.5
ft., from Power Pole No. C-4113.

I set a Brass Cap in found iron pipe marked:



Roger Reece
Roger Reece, County Surveyor

Witnesses: Ray Wytcherley
Mike Gilmore

Date: October 30, 1991