



SCALE 1" = 300'
 Basis of Bearings Solar Observation

LEGEND
 ● = Set 5/8" x 24" I. Pin (tagged R.P.L.S. 638)

MAP OF SURVEY

Located in Section 1, Twp. 38S, R1E
 For: ROGER O'DONAL
 By: George Burrell, P.L.S.
 1379 Brookdale Road
 Medford, Oregon 97504
 Aug. 7, 1992

8-26-92 BF

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
George Burrell
 OREGON
 JULY 10, 1964
 GEORGE R. BURRELL
 638

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR:

Roger O'Donal
14220 E. Antelope Road
Eagle Point, OR 97524

LOCATION:

Section 1, Township 38 South, Range 1 East of the Willamette Meridian

PURPOSE:

To monument the corners and mark the boundary lines of the clients ownership.

PROCEDURE:

A solar observation was taken to establish the Meridian approx. 700 feet West of the East 1/4 corner of Section 1. A random traverse was run to the found controlling subdivisional corners as shown on the accompanying map. The interior 1/16 sectional corners and boundaries were then computed, monumented and true lines established.

Bearing tree's were marked for the following 1/16 corners:

At the C.E. 1/16, a 13" Laurel marked C.E. 1/16 BT bears N 3° 11' E 7.5 feet. A 7" White Fir marked C.E. 1/16 B.T. bears S 62° 23' W 6.9 feet.

At the C.S. 1/16, a 8" White Oak marked C.S. 1/16 B.T. bears N 3° 33' W 45.4 feet. A 6" White Oak marked C.S. 1/16 B.T. bears S 69° 24' E 30.7 feet.

At the W1/16 between Sections 1 and 12, a 6" White Fir marked W1/16 B.T. bears N 78° 36' E 8.7 feet. A 11" D. Fir marked W1/16 B.T. bears S 22° 11' E 3.8 feet.

Bearing and distance was taken to the tree centers at the lower blaze.

BY:

George Burrell, P.L.S.
1379 Brookdale Road
Medford, Oregon 97504
Aug. 7, 1992

