



# Edwards Surveying & Land Planning Inc.

DARREL W. EDWARDS  
OREGON REG. 741  
ARIZONA REG. 9746



DAVID A. EDWARDS  
OREGON REG. 2339

REGISTERED LAND SURVEYORS  
823 WEST 8TH ST.  
MEDFORD, OREGON 97501  
(503) 776-2313 • (503) 471-7059

## 13254

SURVEY NUMBER \_\_\_\_\_

### SURVEY NARRATIVE TO COMPLY WITH CHAPTER 209, PARAGRAPH 205, OREGON REVISED STATUTES

SURVEY FOR: Mike and Kathleen Rustrum  
3254 West Evans Creek Road  
Rogue River, OR 97537

LOCATION: Northeast 1/4 of the Northwest 1/4 of Section 4,  
Township 36 South, Range 4 West of the Willamette  
Meridian in Jackson County, Oregon.

PURPOSE: Survey and monument the outside boundaries of Tax Lots  
500, 600 and 700. Also, to survey a Lot Line Adjustment  
and prepare descriptions creating two tax lots instead  
of three.

PROCEDURE: Traversed between control monuments for Section 4 in  
order to determine the calculated boundaries of the West  
1/2 of the Northeast 1/4 of the Northwest 1/4 of said  
Section 4. Made ties to iron bolts set in Recorded  
Survey Number 1041 and right of way pins set by the  
Jackson County Department of Public Works. Calculated  
position of property lines to be surveyed and  
monumented. Set 5/8 inch by 24 inch steel pins, stamped  
"D.W. EDWARDS-PLS 741", as shown on the accompanying Map  
of Survey.

BASIS OF  
BEARINGS: Recorded Survey Number 1041

EQUIPMENT: Nikon NTD-4 Semi-automatic Theodolite/E.D.M.

DATE  
COMPLETED: October 12, 1992

