

Written narrative to accompany plat for survey NO.

Survey for Dr. Drummond, Medford, Oregon.

Survey made September and October, 1959.

Located in DLC. NO. 68, T 37S. R 2 W. W.M. Jackson County, Ore.

Procedure, From the northwest corner of DLC 66, a pipe found, we ran on solar bearings S 89° 55' 30"W a distance of 1403.68 feet to the southeast corner of D.L.C. NO. 44, a pipe found, thence ran S 0° 00' 10"E, 935.24 feet to the re-established corner for sections 9, 10, 16 and 15, a pipe found, thence ran S 0° 00' 10"E 2768.89 feet to the southeast corner of D.L.C. NO. 43, as determined from a reference pipe found, we then back tracked N 0° 00' 10"W 818.2 feet and set a 5/8" bar for the northwest corner of the tract being surveyed.

Next we found the stine with cross for he northwest corner of D.L.C. NO. 67 and ran S 89° 59' E 1429.5 feet and set a 5/8" bar for the westerly Ell corner of the tract being surveyed, we then tied it to the southwest corner of D.L.C. NO. 43 by running S 89° 59' E a distance of 28.96 feet, thence continuing from the southeast corner of D.L.C. NO. 43, S 89° 59' E we ran to the northeast corner of D.L.C. NO. 68, a distance of 1397.33 feet, then set a 5/8" bar N 89° 59' W, 853.1 feet from said D.L.C. corner.

Next from co-ordinates and computations we ran from the northeast corner of D.L.C. NO. 68, N 0° 05' 30"W on the west line of D.L.C. 66, 752.60 feet and set a 5/8" bar; thence ran N 89° 59' W 84.48 feet and set a 5/8" bar; thence ran N 0° 05' 30"W 65.6 feet and set a 5/8" bar.

Returning to the 5/8" bar previously set N 89° 59' W, 28.96 feet from the southeast corner of D.L.C. NO. 43 we ran S 0° 04' 45"E 1968.90 feet to a point 1.0 foot west of the 5/8" reference bar for the southwest corner of the tract as shown on the plat.

REGISTERED
OREGON
LAND SURVEYOR

L. N. Dow

MAY 6, 1949
L. N. DOW
251

