



LEGEND

- SET 5/8" X 30" REBAR WITH YELLOW PLASTIC CAP MARKED " TEMPLIN LS2359 "
- △ FD. 3" SQUARED WOOD HUB PER BLM ADMINISTRATIVE SURVEY JANUARY 1985
- FD. BRASS CAP PER BLM BOOK PAGE 37
- FD. BRASS CAP PER BLM BOOK PAGE 32
- FD. 3/4" IRON ROD PER RS 3290
- FD. BRASS CAP PER RS 3290
- [] RECORD BEARING/DISTANCE PER BLM ADMINISTRATIVE SURVEY JANUARY 1985
- () RECORD BEARING/DISTANCE PER RS 3290
- INDICATES LINES BLAZED AND PAINTED RED
- X— INDICATES EXISTING FENCE LINE

BEARINGS BASED UPON BLM ADMINISTRATIVE SURVEY JANUARY 1985

** NARRATIVE IS SEPARATE DOCUMENT **

33 - 2W - 27

**** RECEIVED ****
Date 3-9-93 By RT
This survey consists of:
— 1 sheet(s) Map
— 1 page(s) Narrative
JACKSON COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR
Richard G. Templin
OREGON
RICHARD G. TEMPLIN
2359
My Certificate Expires Dec. 31, 19 94

RICHARD TEMPLIN LAND SURVEYING
2042 SANDRA PL 776-0991 & 474-7720 MEDFORD, OREGON
MAP OF SURVEY
LOCATED IN
SE1/4 OF SECTION 27, T.33S., R.2W., W.M.
JACKSON COUNTY, OREGON
SURVEYED FOR: BOISE CASCADE CORP. DATE: MARCH 8, 1993
P.O. BOX 100
MEDFORD, OREGON 97501

FILE: " BOISE27.DW2 "

RICHARD G. TEMPLIN
PROFESSIONAL LAND SURVEYOR
2042 Sandra Pl.
Medford, Oregon 97504
(503) 776-0991 • 474-7720

13399

NARRATIVE

Survey No. _____

SURVEY FOR: Boise Cascade Corp.
P.O. Box 100
Medford, Oregon 97501

LOCATION: Se 1/4 of Section 27, Township 33 South, Range 2
West, of the Willamette Meridian, Jackson County,
Oregon.

PURPOSE: To run and mark true line as shown on
accompanying plat.

DATE: March 8, 1993

BASIS OF BEARING: Bearings based upon B.L.M.
Administrative Survey, Jan. 1985.

PROCEDURE Tied the South and East Quarter corners, along
with the SE corner of Section 27, S 1/16 corner
set on R.S. 3290 and the B.L.M. C 1/4 position.
Ties to the S 1/4 and the E 1/4 corners checked
very close to the B.L.M. Administrative survey.
I accepted the C 1/4 position, along with the S
1/16 corner set on R.S. 3290. Computed the SE
1/16 corner position and set:

A 5/8"x 30" rebar with yellow plastic cap marked,
"TEMPLIN LS 2359", from which I scribed the
following bearing tree:
A Cedar, 10" diameter bears N 57°E, 13.1 feet,
scribed " SE1/16S27" "BT".
A Cedar, 9" diameter bears N 57°W, 10.6 feet,
scribed " SE1/16S27" "BT".

I then computed the E 1/16 corner between Section
27 and 34 position and set:

A 5/8"x 30" rebar with yellow plastic cap marked,
"TEMPLIN LS 2359", from which I scribed the
following bearing tree:
A White Oak, 10" diameter bears N 17°W, 20.1
feet, scribed " E1/16S27" "BT".
A Douglas Fir, 12" diameter bears S 86°W, 50.9
feet, scribed " E1/16S34" "BT".

I then ran true line between corners, as shown,
blazed, painted, flagged and tagged said lines.

** RECEIVED **

Date 3-9-93 By RS

This survey Consists of:

1 sheet(s) Map

1 page(s) Narrative

JACKSON COUNTY
SURVEYOR

REGISTERED
PROFESSIONAL
LAND SURVEYOR

My Li

OREGON
JULY 26, 1988
RICHARD G. TEMPLIN
2359

My Certificate Expires Dec. 31, 19 94