



**LEGEND**

- SET 5/8" X 30" REBAR WITH YELLOW PLASTIC CAP MARKED " TEMPLIN LS2359 "
- △ FD. 3" SQUARED WOOD HUB PER BLM ADMINISTRATIVE SURVEY JANUARY 1985
- FD. BRASS CAP PER BLM BOOK PAGE 37
- FD. BRASS CAP PER BLM BOOK PAGE 32
- FD. 3/4" IRON ROD PER RS 3290
- ⊙ FD. BRASS CAP PER RS 3290
- [ ] RECORD BEARING/DISTANCE PER BLM ADMINISTRATIVE SURVEY JANUARY 1985
- ( ) RECORD BEARING/DISTANCE PER RS 3290
- INDICATES LINES BLAZED AND PAINTED RED
- X— INDICATES EXISTING FENCE LINE

BEARINGS BASED UPON BLM ADMINISTRATIVE SURVEY  
JANUARY 1985

\*\* NARRATIVE IS SEPARATE DOCUMENT \*\*

**\*\* RECEIVED \*\***  
Date 3-12-93 By RF  
This survey consists of:  
1 sheet(s) Map  
1 page(s) Narrative  
JACKSON COUNTY  
SURVEYOR

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Richard G. Templin*  
RICHARD G. TEMPLIN  
2359  
My Certificate Expires Dec. 31, 19 94

**RICHARD TEMPLIN LAND SURVEYING**  
2042 SANDRA PL 776-0991 & 474-7720 MEDFORD, OREGON  
**CORRECTIVE  
MAP OF SURVEY**  
LOCATED IN  
SE1/4 OF SECTION 27, T.33S., R.2W., W.M.  
JACKSON COUNTY, OREGON  
SURVEYED FOR: BOISE CASCADE CORP. DATE: MARCH 12, 1993  
P.O. BOX 100  
MEDFORD, OREGON 97501

33 - 2W - 27

FILE: " BOISE27.DW2 "

**RICHARD G. TEMPLIN**  
PROFESSIONAL LAND SURVEYOR

2042 Sandra Pl.  
Medford, Oregon 97504  
(503) 776-0991 • 474-7720

CORRECTIVE SURVEY

NARRATIVE

Survey No. 13403

SURVEY FOR: Boise Cascade Corp.  
P.O. Box 100  
Medford, Oregon 97501

LOCATION: SE 1/4 of Section 27, Township 33 South, Range 2 West, of the Willamette Meridian, Jackson County, Oregon.

PURPOSE: To correct that survey recorded March 10, 1993 in the Jackson County Surveyor's office as R.S. 13399.

DATE: March 12, 1993

BASIS OF BEARING: Bearings based upon B.L.M. Administrative Survey, Jan. 1985.

PROCEDURE Tied the South and East Quarter corners, along with the SE corner of Section 27, S 1/16 corner set on R.S. 3290 and the B.L.M. C 1/4 position. Ties to the S 1/4 and the E 1/4 corners checked very close to the B.L.M. Administrative survey. I accepted the C 1/4 position, along with the S 1/16 corner set on R.S. 3290. I then computed the E 1/16 corner between Section 27 and 34 position and set:

A 5/8"x 30" rebar with yellow plastic cap marked, "TEMPLIN LS 2359", from which I scribed the following bearing tree:  
A White Oak, 10" diameter bears N 17°W, 20.1 feet, scribed " E1/16S27" "BT".  
A Douglas Fir, 12" diameter bears S 86°W, 50.9 feet, scribed " E1/16S34" "BT".

I then set the NW corner of that tract of land described in 89-28675, of the Official Records of Jackson County, Oregon:  
A 5/8"x 30" rebar with yellow plastic cap marked, "TEMPLIN LS 2359", from which I scribed the following bearing trees:

A Cedar, 10" diameter bears N 57°E, 13.1 feet, scribed " NWPC" "BT".  
A Cedar, 9" diameter bears N 57°W, 10.6 feet, scribed " NWPC" "BT".

I then ran true line between corners, as shown, blazed, painted, flagged and tagged said lines.

\*\* RECEIVED \*\*

Date 3-12-93 By RF

This survey Consists of:

1 sheet(s) Map

1 page(s) Narrative

JACKSON COUNTY  
SURVEYOR

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*M G L*

OREGON  
JULY 26, 1988  
RICHARD G. TEMPLIN  
2359

My Certificate Expires Dec. 31, 19 94